CHINTALAPATI HOLDINGS PVT LTD
18, BLG3, ILABSCENTRE
SOFTWAREUNITS LAYOUT,MADHAPUR,
Ranga Reddy, Telangana, 500081

PROFORMA INVOICE

Supplier Code :
Supplier Name and Address:
NUCLEUS SATELLITE COMMUNICATIONS (MADRAS) PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati Andhra Pradesh-517541
GST: 37AALCK8658A1Z8

PI NO: PI /2025-26/003
PI Date 07.03.2026
Reference : **PO/25-26/0085**
Mode of Transport: NA
Incoterms : NA

GST : **36AABCC5085D1ZV**

Please supply the following materials subject to terms and conditions. Kindly acknowledge receipt of this order

Sl.No	Item Code	Description	HSN/SAC code	Qty	UOM	Unit price (Rs)	Amount in (Rs)
1		**LAYING OF BT ROADS UPTO GSB** Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 30 cm depth,dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with lead upto 50 metres.	9954	1950	Cum	354	689,325
2		Forming sub grade with embankment barrowed useful selected earth having MDD of not less than 1.75 Gms/CC from out side road boundary by mechanicalmeans with all leads and lifts including prewatering of soil at barrow area, removal of top soil, excavation of soils at barrowed area, conveyance of soil, depositing the soils on the embankment, spreading soils, beaking clods, sectioning and consoilidation with vibratory road roller @ OMC to meet requirement of table 300-2 of MoRT&H, including all hire and operational charges of T&P and complete for finished item of work as per T&P and complete for finished item of work as per MoRT&H specification 305 (5th revision).	9954	1176	Cum	253	296,940
3		Providing, Laying, Spreading and compacting 230mm graded GSB (GRANULAR SUB BASE) conforming to the MoRTH Specifications for Road and Bridge Works[23] as specified in IRC 37-2018 (4th Revision),including cost of all materials and including premixing the material with water at OMC in Mechanical mix plant carriage of mixed material by tipper to site , laying in uniform layers with paver in base courses on well prepared surface and compacting with Vibratory roller to acheive the desired density etc., as directed by the Engineer-in-Charge and as per MoRT&H specification 406 (5th revision) for finished item of work	9954	2047	Cum	909	1,860,723

Total Amount Before Tax(Rs) :	2,846,988
GST Value	512,458
Po Value (Rs) :	3,359,446
50% Advance Payable as per F	**1,423,494**

Total Amount in Words: Fourteen Lakh Twenty Three Thousand Four Hundred Ninety Four Only

Authorised Signatory