NUCLEUS SATELLITE COMMUNICATIONS (MADRAS) PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

Purchase Order

Supplier Code :
Supplier Name and Address:

CHINTALAPATI HOLDINGS PVT LTD

18, BLG3, ILABSCENTRE,
SOFTWAREUNITSLAYOUT,MADHAPUR,
Ranga Reddy, Telangana, 500081
Email:
GST: 36AABCC5085D1ZV

PO Number : **PO/25-26/086**
PO Date : **17-02-2026**

Payment terms : **50% advance of PO Value along with (PO)**
:45% on completion of Earthworks & Laying of GSB
:5% on completion of work

Delivery time : Work completion45 days from PO receipt date
Mode of Transport: NA
Incoterms : NA

GST : **37AAACN9960D2ZA**

Please supply the following materials subject to terms and conditions. Kindly acknowledge receipt of this order

Sl.No	Item Code	Description	HSN/SAC code	Qty	UOM	Unit price (Rs)	GST% Rate	GST% Amount	Amount in (Rs)
		LAYING OF BT ROADS							
		BILL OF QUANTITIES							
A4		Providing, Laying, Spreading and compacting 200mm graded HBG crushed stone aggregate to Wet Mix macadem specification (5th Revision) as per Table 400-13, including cost of all materials and including premixing the material with water at OMC in Mechanical mix plant carriage of mixed material by tipper to site , laying in uniform layers with paver in base courses on well prepared surface and compacting with Vibratory roller to acheive the desired density etc., as directed by the Engineer-in-Charge and as per MoRT&H specification 406 (5th revision) for finished item of work	9954	1,780	Cum	2,084	18%	6,67,595	37,08,861
A5		Providing and applying prime coat with bitumen emulsion (SS1) Bulk using emulsion pressure distributor on prepared surface of granular base including clearing of road surface and spraying emulsion at the rate of 0.70 kg/sqm using emulsion pressure distributor for finished item of work etc., complete as per MoRT&H Specification 502 (5th revision) and as directed by the Engineer-in-charge	9954	8,900	Sqm	63	18%	1,00,317	5,57,318
A6		Providing and applying tack coat with bitumen VG 10 (Bulk) using Bitumen pressure distributor at the rate of 0.20 kgs per sqm on the prepared bituminous surface cleaned with mechanical broom for finished item of work as per MoRT&H Specification 503 (5th revision) and as directed by the Engineer-in-Charge.	9954	8,900	Sqm	16	18%	25,888	1,43,824
A7		Providing and laying of 30mm dense Bituminous Concrete with 100 - 120 TPH batch type hot mix plant producing an average output of 75 tones per hour using hard blasted granite crushed aggregates of Grading – II as per Table 500-17 of specification 507 of MoRT&H (5th revision), premixed with Bituminous binder of VG 30 Grade @ 5.4 % of mix and filler, transporting the hot mix to work site, laying with hydrostatic sensor paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRT&H Specification 507 (5th revision) complete for finished item of work in all respects as directed by Engineer in Charge	9954	270	Cum	12,928	18%	6,28,301	34,90,560

A8		Providing and applying tack coat with bitumenemulsion rapid setting over the prepared surface laying BC @ 2 Kg/10Sqm including cleansing the road surfacewith mechanical Broomand air compressor and applying uniformity with the aid of emulsion pressure sprayer including cost and conveyance of bitumen emulsion, labour charges, cleaning charges, alltaxes hire charges and operational charges of all T & Pnecessary to complete the finished item of work as per MoRT&H Specification 503 (5threvision) and as directed by the Engineer-in-Charge.	9954	8,900	Sqm	14	18%	22,652	1,25,846
A9		Providing and laying of 40mm Dense Graded Bituminous Macadam with 100 - 120 TPH batch type hot mix plant producing an average output of 75 tones per hour using hard blasted granite crushed aggregates of Grading - II as per table 500-10 of MoRT&H Specification 505 (5th revision) premixed with bituminous binder of VG 30 grade @ 4.50% of weight of total mixture, transported to site, laid over a previously prepared surface with a hydrostatic paver finisher with sensor control to the required grade, level and alignment and rolled as per Clauses 501.6 and 501.7 to achieve the desired compaction for finished item of work as directed by the Engineer-in-Charge including hire and operational charges all T&P and all other contingent charges necessary including cost of (excluding seigniorage) charges of all materials etc., complete in all respects as directed by Engineer-in-Charge and as per MoRT&H specification No. 505 (5th Revision)	9954	350	Cum	11,918	18%	7,50,834	41,71,300

Total Amount Before Tax(Rs) :	1,21,97,709
GST Value :	21,95,588
Po Value (Rs) :	**1,43,93,297**

Total Amount in Words: **One Crore Forty Three lakhs Ninety three thousand and Two hundred and Ninety Seven only**

B.N.

Jayakishore.L

Prepared By

Verified By

Approved By

Terms and Conditions:

Start of work:
Once the supplier receipt of PO acceptance has to be made within 24 hrs and start of work to be carried out immediately (within 1-2 days)

Delivery & Execution:
Supplier has to complete the work on or before 45 days from receipt of PO. PO receipt must be acknowledged through electronic mail. Work should be carried out as per work schedule given by the supplier. Supplier exceeds the time line of completion may leads to LD clause as per Industry standards

Specification and changes:
No changes should be made against the scope if any necessity changes to be made during the execution should be discussed and agreed with customer without affecting the completing date and should the incorporate within the Po prices

Cancellation:
Once the supplier agreed and acknowledge the PO which cannot be cancelled during the execution time by the supplier at any cause. Acceptance criteria must includes consideration of all factors.

Inspection of product:
Brand/make of materials to be supplied and used for the scope of work should be Honer as per the PO. Deviations shall not be accepted and rejected by the customer moreover it should not make any loss of time interms of reprocurement and rework.

Warrenty:
Supplier should pass on the warranty of the raw materials and warranty of work. Warranty period of 5-7 years from the date of installation includes any damages, distortion and dismantling of any element due to the natural climatic conditions.

LD Clause:
The supplier agrees that the Late Delivery/Execution for the delayed work @2% of work order for every week and maximum of 8-10% upto 1 month shall be paid to Buyer

Billing to:
NUCLEUS SATELLITE COMMUNICATIONS (MADRAS) PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

Shipping to:
NUCLEUS SATELLITE COMMUNICATIONS (MADRAS) PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

B. N.	Jayakishore.L	
Prepared By	Verified By	Approved By