YANVIOR TECHNOLOGIES PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

Purchase Order

Supplier Code :
Supplier Name and Address:

Vat Tech Enggineering . Pvt Ltd

No 38, Karpagambal Nagar
Nandhivaram Guduvancherri 603202
Tamilnadu,India
Email:
GST: 33AAECV6181C1ZI

PO Number : **PO/26-27/0021**
PO Date : **03-04-2026**
Payment terms : **30% Advance with PO**
60 % Against delivery of materials at site
10% After testing and commisioning
AC VRF and AHU unit 100% Advance payment
Delivery time : **4 weeks**
Mode of Transport: **Road**
Incoterms : **Deliver to Sricity**
GST : **37AAACN9960D2ZA**

Please supply the following materials subject to terms and conditions. Kindly acknowledge receipt of this order

Sl.No	Item Code	Description	HSN/SAC code	Qty	UOM	Unit price (Rs)	GST%		Amount in (Rs)
							Rate	Amount	
		Cafeteria							
A		**SUPPPLY OF VRF OUTDOOR UNITS**							
1		24HP Outdoor units	84159000	1	Nos	4,33,599.00	18%	78,047.8	4,33,599.00
B		**SUPPLY OF VRF INDOOR UNITS/AHU AND ACCESSORIES**							
2		3.2 TR Cassette Indoor unit with front panel and remote control	84159000	6	Nos	48,165.00	18%	52,018.2	2,88,990.00
		SUPPLY,INSTALLATION & TESTING OFVRV LOW SIDE WORKS							
1		Installation charges							
a		**Outdoor unit installation charges**	995463	1	Nos	6,900.00	18%	1,242.0	6,900.00
b		**Installation charges for VRV Indoor units.**	995463	6	Nos	3,450.00	18%	3,726.0	20,700.00
2		Soft/Hard drawn Refrigerant Copper piping between Indoor & Outdoor units covered with suitable Nitrile Rubber Insulation 13/19 mm thick .	995463	60	Rmt	2,185.00	18%	23,598.0	1,31,100.00
3		**Control Cabling**	995463						
a		2 core 1.0 Sq.mm flexible control cable & PVC conduits to	995463	115	Rmt	149.00	18%	3,084.3	17,135.00
4		PVC drain piping with supports, clamps and 6mm thick Nitrile rubber tube insulation of following sizes	995463						
a		32 mm dia	995463	50	Rmt	276.00	18%	2,484.0	13,800.00
5		R-410A Gas.	995463	16	Kgs	1,035.00	18%	2,980.8	16,560.00
6		Indoor Unit Necessary Y Joints	995463	5	Nos	345.00	18%	310.5	1,725.00
7		Outdoor Unit Necessary Y Joints	995463	1	Nos	690.00	18%	124.2	690.00
8		**Unit lifting shifting , positioning Vaccumeising , Pressure testing and Commissioning charges**	995463	24	HP	1,150.00	18%	4,968.0	27,600.00
9		Cassette Indoor Unit supporting from roof threaded rod,nut & washer etc (structural support by Client)	995463	6	Nos	1,150.00	18%	1,242.0	6,900.00
10		Copper pipe supporting from roof threaded rod,nut & washer etc (structural support by Client)	995463	1	Lot	6,900.00	18%	1,242.0	6,900.00
11		Outdoor Unit MS stand stool type	995463	2	Nos.	9,200.00	18%	3,312.0	18,400.00
12		Civil work for Outdoor unit Leg	995463	2	Nos.	2,300.00	18%	828.0	4,600.00
13		CABLE / PIPE TRAYS : Supply & Installation of pre-galvanized sheet steel perforated cable tray along with top cover. The cable tray shall include necessary supports and other accessories.							
a		200mm wide x 100 mm height only outside building	995461	15	Rmt	977.00	18%	2,637.9	14,655.00
26		Supply & Installation of MS Supports for VRV IDU ETC	995463	300	Kg	207.00	18%	11,178.0	62,100.00
27		Transporation Charges	996511	1	lot	11,500.00	18%	2,070.0	11,500.00

Total Amount Before Tax(Rs) :	10,83,854.0
GST Value :	1,95,093.7
Po Value (Rs) :	**12,78,948**

Total Amount in Words: **Twelve Lakhs Seventy Eight thousand Nine Hundred and Forty Eight only**