YANVIOR TECHNOLOGIES PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

Purchase Order

Supplier Code :
Supplier Name and Address:

SVN ENGINEERING SERVICES

No:1-190, Mallavaripalem East,
Sri City, Satyavedu Mandal,
Tirupathi District, AP-517588
Email:svnengineeringservices25@gmail.com
GST: 37AQOPN2483N1Z0

PO Number : **PO/26-27/0004**
PO Date : **01-04-2026**
Payment terms : **50% Advance With PO & 50% After completion of work**
Delivery time : **4 weeks**
Mode of Transport: **NA**
Incoterms : **NA**
GST : **37AAACN9960D2ZA**

Please supply the following materials subject to terms and conditions. Kindly acknowledge receipt of this order

Sl.No	Item Code	Description	HSN/SAC code	Qty	UOM	Unit price (Rs)	GST%		Amount in (Rs)
							Rate	Amount	
		Canteen Building Glass Partition ,Modular Puff Ceiling and Civil work							
1		8.mm Glass partition: Providing and fixing side hung Patch Fitting Glass partition with 12mm thick Clear Toughened glass including approved operating hardware's, SS patch fittings of wood make for frameless patch fitting glass for fixed panel on top as detailed in drawings. The rate shall include transportation, etc. complete as directed	995441	1115	Sq.Ft	300.00	18%	60,210.00	3,34,500.00
2		Providing and Installation of Powder coated Aluminium Frame having 1.2 mm thickness Size: 2.5 inches x 1.5 Inches	995441	1115	Sq.Ft	120.00	18%	24,084.00	1,33,800.00
3		8.mm Glass door: Providing and fixing side hung Patch Fitting Glass doors with 12mm thick Clear Toughened glass including approved operating hardware's, SS patch fittings of wood make with brush steel finish SS handles of size 12" height, patch lock, floor springs for frameless patch doors for the opening size mentioned below. Openable shutters with fixed panel on top as detailed in drawings. The rate shall include transportation, etc. complete as directed 2000 X 2100 MM (DOUBLE DOOR)	995441	1	No	68,500.00	18%	12,330.00	68,500.00
4		GYPSUM DOUBLE WALL PARTITION: Providing and fixing 12.5.mm Gypboard both side single ply and 48.mm Metal stud, 50.mm floor channel partition system 75mm thick consisting with one coat joint putty and trucare interior wall primer and two coat tractor emulsion (Asian paints) /For Steps and GF Cabins	995441	300	Sq.Ft	150.00	18%	8,100.00	45,000.00
5		Providing and Installation Of Frosted Film For Glass Partition and Glass Door	995441	1115	Sq.Ft	80.00	18%	16,056.00	89,200.00
6		**Ceiling -Modular Puff Partition** Supply and Installation of sandwiched GI Powder coated walkable false ceiling of minimum 50mm Thk. Both side cladding of PU powder coated (60-80 microns) 0.6 mm thick Galvanize iron sheets (hot dipped with zinc coating of 120 gsm) with PUF as infill of density not less than 40 Kg/m3 .The load bearing capacity to be not less than 150kg/m2. The clean room panel should meet the Euro classes minimum reaction to fire B-s3,d0. Necessary stiffners to be provided as per manufacturer's standard and complete in all respects including, supports, hangers, sealants, etc.	995441	2100	Sq.Ft	249.00	18%	94,122.00	5,22,900.00

7		Providing and Installation of Ceiling Panel Aluminium H-grid, Turn Buckle for every 3 Mtr Intervals	995441	80	Rmt	765.00	18%	11,016.00	61,200.00
8		Providing and Installation of Threared Rod 4 to 5 Rmt each support, GI Clamp for Purlin support, Screw, Nut, washer & Silicon etc.	995441	2100	Sq.Ft	15.00	18%	5,670.00	31,500.00
9		Providing and Installation of 50 x 50 mm metallic coving corners with Epoxy Powder coated/PU powder coated (60-80 microns) finish of matching colour with panel / ceiling and air tight with sealant at wall to wall with corner 2D or 3D	995441	10	Nos	200.00	18%	360.00	2,000.00
10		Providing and Installation of Aluminium/GI Coving for Ceiling to Gridth 150 MM	995441	56	Rmt	725.00	18%	7,308.00	40,600.00
		Cutouts							
11		Cutouts for Light Fixtures and Diffucers , consider 150 Lights and 150 Diffucers	995441	20	Nos	210.00	18%	756.00	4,200.00
12		C Flashing for Cutouts - with Powder Coated	995441	48	Rmt	225.00	18%	1,944.00	10,800.00
		Civil Work							
13		Providing and laying of premium quality Vitrified matt Finish tiles of size 2 feet x2 feet of approved make floor semi matt finished colour With Application of tile Adhasive and Epoxy Grout.	995428	2225	Sq.Ft	120.00	18%	48,060.00	2,67,000.00
14		Providing and laying of premium quality Skirting Tiles Matt finish with Height 100 MM of approved make floor semi matt finished colour With Application of tile Adhasive and Epoxy Grout.	995428	30	Rmt	350.00	18%	1,890.00	10,500.00
15		Brick Masonry in CM (1:8) with 2nd class Bricks traditional size 23 x 11 x 7 cms including cost and conveyance charges of materials and labour charges etc., complete.	995428	400	Sq.Ft	250.00	18%	18,000.00	1,00,000.00
16		Plastering with CM (1:3), 20 mm thick (Impervious Coat) including cost and conveyance of all materials and all labour charges etc., complete	995428	800	Sq.Ft	65.00	18%	9,360.00	52,000.00
17		Providing and Installation of Granite Laying For Floor having Size: 100 MM	995428	28	Rmt	650.00	18%	3,276.00	18,200.00
18		Plumbing-Drainage Work For Hand Wash Area and Vessel Wash Area, the Work Includes Water Supply Pipe and Drainage Pipe	995428	1	Lmps	30,000.00	18%	5,400.00	30,000.00
		MS Supports							
19		Supply, fabricate and erect in position structural steel work for False ceiling and partition supports. Structure should be painted with one coat of primer and 2 coats of Enamel paint. Note: The rate Includes the field drilling / welding wherever necessary	995455	1350	Kgs	110.00	18%	26,730.00	1,48,500.00

Total Amount Before Tax(Rs) :	19,70,400.00
GST Value :	3,54,672.00
Po Value (Rs) :	**23,25,072.00**

Total Amount in Words: **Twenty Three Lakhs Twenty Five thousand Seventy two only**

Prepared By	Verified By	Approved By
Parthiban R	Arunkumar B N	Jayakishore L
Purchase Engineer	Plant Engineering -Head	AVP Operations

Jayakishore Digitally signed by Jayakishore Date: 2026.04.02 12:06:51 +05'30'

Terms and Conditions:

1. Warranty 1 year for the items supplied
2. All the items should supply with specific brand mentioned in the quote
3. Items must be deliver on time as specified in the Po

Billing to:
YANVIOR TECHNOLOGIES PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

Shipping to:
YANVIOR TECHNOLOGIES PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

Prepared By	Verified By	Approved By
Parthiban R	Arunkumar B N	Jayakishore L
Purchase Engineer	Plant Engineering -Head	AVP Operations