SCIC VENTURES LLP

BUILDING NO 3 PLOT NO 18
ILABS CENTRE, SOFTWARE UNITS' LAYOUT, BESIDE INORBIT MALL
Madhapur, Hyderabad-500081
Email: praveen.kumar@scicventures.com

Purchase Order

Supplier Code :
Supplier Name and Address:

SVN ENGINEERING SERVICES

No:1-190, Mallavaripalem East,
Sri City, Satyavedu Mandal,
Tirupathi District, AP-517588
Email:svnengineeringservices25@gmail.com
GST: 37AQOPN2483N1Z0

PO Number : **PO/25-26/0050**
PO Date : **05-02-2026**
Payment terms : **50 % Advance Along With PO and 50 % After Completion work.**
Delivery time : **4 weeks**
Mode of Transport: **NA**
Incoterms : **NA**

GST : 36AFPFS5893H1Z5

Please supply the following materials subject to terms and conditions. Kindly acknowledge receipt of this order

Sl.No	Item Code	Description	HSN/SAC code	Qty	UOM	Unit price (Rs)	GST%		Amount in (Rs)
							Rate	Amount	
1		Supply and Installation of **Wall Ribbed Puff** Panels of minimum 50 mm Thk. Both side cladding of PPGI sheet of 0.5mm thick Galvanize iron sheets (hot dipped with zinc coating of 120 gsm) with PUF as infill of density not less than 40 Kg/m3 . Hidden Tongue and Groove with Necessary stiffners to be provided as per manufacturer's standard and complete in all respects.	995428	3500	Sq.Feet	281.20	18%	1,77,156.00	9,84,200.00
2		Removing of Existing Rolling Shutter with Gas cutting, and removing the structure	995428	4	Nos	9,295.75	18%	6,692.94	37,183.00
3		Removing of Existing Puff Partition panels and Move to scrap	995428	1500	Sq.Feet	33.25	18%	8,977.50	49,875.00
		Rolling Shutter MS Supports							
4		Supply, fabricate and erect in position structural steel work for Rolling Shutters Structure should be painted with one coat of primer and 1 coats of Enamel paint. Note: The rate Includes the field drilling / welding wherever necessary.	995428	810	Kgs	137.75	18%	20,083.95	1,11,577.50
		Glass Work							
5		Removing of old Glass partition with 12mm thick Clear Toughened glass in labour charges	995428	1	Lumps	42,750.00	18%	7,695.00	42,750.00
6		Providing and fixing SS IMAX fittings Change and labour charges	995428	20	Nos	3,595.00	18%	12,942.00	71,900.00
7		Service Charges For SS IMAX Glass Windows	995428	55	Nos	418.00	18%	4,138.20	22,990.00
8		Providing and fixing 24.mm Glass Toughened glass including approved operating hardware's, SS patch fittings Change	995428	1	Nos	9,381.25	18%	1,688.63	9,381.25

Total Amount Before Tax(Rs) :		13,29,856.75
GST Value	:	2,39,374.22
Po Value (Rs)	:	**15,69,230.97**

Total Amount in Words: **Fifteen lakhs Sixty nine thousand Two hundred and Thirty only**

B. N. Reddy.
Prepared By

Jayakishore
Verified By

Approved By

Terms and Conditions:

1. Work shoud complete within the time line quoted.
2. Scope of work quoted must cover 100%
3. All the scraps disposal has to be done clearly

Billing to:
SCIC VENTURES LLP
BUILDING NO 3 PLOT NO 18
ILABS CENTRE, SOFTWARE UNITS' LAYOUT, BESIDE INORBIT MALL
Madhapur, Hyderabad-500081

Shipping to:
NUCLEUS SATELLITE COMMUNICATIONS (MADRAS) PRIVATE LIMITED
Flat No.: 465,RCITRUS DRIVE
MOPURU PALLI VILLAGE, SATYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

Prepared By	Verified By	Approved By
B. N.	Jayakishan	