PROFORMA INVOICE

ORIGINAL FOR RECIPIENT

SVN ENGINEERING SERVICES

GSTIN 37AQOPN2483N1Z0
1-190
SRICITY, Satyavedu
Tirupati, ANDHRA PRADESH, 517588

Pro Forma Invoice #: **SVN/PFI-49**

Proforma Invoice Date: **05 Apr 2026**

Customer Details:
YANVIOR TECHNOLOGIES PVT LTD
GSTIN: 37AAACN9960D2ZA
Ship to : 465
CITRUS DRIVE, Sri City
Tirupati
37-ANDHRA PRADESH-517541
India

Billing Address:
465
CITRUS DRIVE, Sri City
Tirupati, ANDHRA PRADESH, 517541

Shipping Address:
YANVIOR TECHNOLOGIES PVT LTD
465
CITRUS DRIVE, Sri City
Tirupati, ANDHRA PRADESH, 517541

Place of Supply:
37-ANDHRA PRADESH

Reference: Civil Foundation For GRP Water Tank and VCB Foundation

PO Number: **PO/26-27/0011**

PO Date: **01-04-2026**

#	Item	Rate / Item	Qty	Taxable Value	Tax Amount	Amount
1	Site Development and Layout Marking-Bush removing, Cleaning, Sactioning and Levelling work. The Work Includes Manpower and JCB SAC: 995428	102.60	118 M2	12,106.80	2,179.22 (18%)	14,286.02
2	Excavation in all types of soil including dense soil, disintegrated / weathered / Laterite / soft rock (Poclainable) by Manual / Mechanical means. Rate shall include for materials, labours, equipment, tools & plant, transportation, site clearances, setting out, shoring-, strutting, dewatering, bailing out or pumping out of water in the excavation from rain / sub soil, slips and falls in excavation, slinging or supporting pipes electric cables etc met during excavation,manual excavation for leveling, dressing the edges, with all leads inside and outside and lifts including loading unloading, machinery and equipments and dressing to proper level and graded as required etc, SAC: 995428	1,068.30	60 M3	64,098.00	11,537.64 (18%)	75,635.64

#	Item	Rate / Item	Qty	Taxable Value	Tax Amount	Amount
3	Providing and Laying of GSB and is constructed with well graded Granular Soil, maintaining suitable moisture content and compacted in layers with 100 mm thickness, and Compaction is done using of Earth Hammer. SAC: 995428	1,500.00	25 M3	37,500.00	6,750.00 (18%)	44,250.00
4	Providing and laying required thickness of controlled plain cement concrete of M10 grade using 20 mm and down size coarse graded hard stone aggregate for levelling course in foundation at any mass concrete and other similar works at all levels and heights, elevations, mechanical controlled mixing, transporting and placing, pumping at all lifts, vibrating, compacting, levelling, curing, shuttering, dewatering wherever necessary, the cost of all materials, labour, leads and lifts, tools and plant, machineries etc., complete as per specifications. SAC: 995428	6,140.70	16 M3	98,251.20	17,685.22 (18%)	1,15,936.42
5	Providing and laying in situ cement concrete of trap metal for R.C.C. (M-25) work in foundations of R.C.C. columns and steel stanchions including dewatering, formwork, compaction finishing and curing etc. complete. (excluding reinforcement and structural steel) Floor and Columns. SAC: 995428	8,528.40	72 M3	6,14,044.80	1,10,528.06 (18%)	7,24,572.86
6	Providing and fabricating TMT/ twisted bars all diameters for reinforcement in RCC Column works as per requirement and given 150mm spacing inclusive of binding wire, transporting to the site from the stores, straightening, cleaning, cutting, bending to shapes and lengths as per details & placing in position with binding wires at all levels. Floor and Columns. SAC: 995428	106.20	5,250 KGS	5,57,550.00	1,00,359.00 (18%)	6,57,909.00

#	Item	Rate / Item	Qty	Taxable Value	Tax Amount	Amount
7	Back filling the excavated earth with Sand in trenches, sides of foundations & basement by watering and ramming including all operational, incidental, labour charges, hire charges of T&P etc complete including cost and conveyance of material and watering charges etc complete for finished item of the work SAC: 995428	1,698.30	130 M3	2,20,779.00	39,740.22 (18%)	2,60,519.22
8	Plastering and Surface Treatment 18-mm thick with mix ratio of 1:6, on both side of Block work. SAC: 995428	670.50	300 M2	2,01,150.00	36,207.00 (18%)	2,37,357.00

Taxable Amount	₹18,05,479.80
CGST 9.0%	₹1,62,493.18
SGST 9.0%	₹1,62,493.18
Round Off	-0.16
Total	**₹21,30,466.00**
50% Advance	**₹10,65,233.00**

Total Items / Qty : 8 /5,971 Total amount (in words): INR Ten Lakhs, Sixty Five Thousand, Two Hundred And Thirty-Three Rupees Only.

Bank Details:

Bank:	**AXIS BANK LTD**
Account Holder:	**SVN ENGINEERING SERVICES**
Account #:	**924020017798056**
IFSC Code:	**UTIB0005062**
Branch:	**Chilamathur**

For SVN ENGINEERING SERVICES

Authorized Signatory

Notes:

Payment terms :50% Advance With PO & 50% After completion of work