NUCLEUS SATELLITE COMMUNICATIONS (MADRAS) PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

Purchase Order

Supplier Code :
Supplier Name and Address:

SVN ENGINEERING SERVICES

No:1-190, Mallavaripalem East,
Sri City, Satyavedu Mandal,
Tirupathi District, AP-517588
Email:svnengineeringservices25@gmail.com
GST: 37AQOPN2483N1Z0

PO Number : **PO/25-26/0075**
PO Date : **25-02-2026**
Payment terms : **50% Advance With PO & 50% After completion of work**
Delivery time : **4 weeks**
Mode of Transport: **NA**
Incoterms : **NA**

GST : **37AAACN9960D2ZA**

Please supply the following materials subject to terms and conditions. Kindly acknowledge receipt of this order

Sl.No	Item Code	Description	HSN/SAC code	Qty	UOM	Unit price (Rs)	GST%		Amount in (Rs)
							Rate	Amount	
		Utility Building Construction-Civil Work							
1		Site Development and Layout Marking-Bush removing, Cleaning, Sactioning and Levelling work. The Work Includes Manpower and JCB	995428	320	M2	102.60	18%	5,909.76	32,832.00
2		Excavation in all types of soil including dense soil, disintegrated / weathered / Laterite / soft rock (Poclainable) by Manual / Mechanical means.Rate shall include for materials, labours, equipment, tools & plant, transportation, site clearances, setting out, shoring, strutting, dewatering, bailing out or pumping out of water in the excavation from rain / sub soil, slips and falls in excavation, slinging or supporting pipes electric cables etc met during excavation,manual excavation for leveling, dressing the edges, with all leads inside and outside and lifts including loading unloading, machinery and equipments and dressing to proper level and graded as required etc.	995428	45	M3	1,068.30	18%	8,653.23	48,073.50
3		Providing and Laying of GSB and is constructed with well graded Granular Soil, maintaining suitable moisture content and compacted in layers with 100 mm thickness, and Compaction is done using of Earth Hammer.	995428	62	M3	810.00	18%	9,039.60	50,220.00
4		Providing and laying required thickness of controlled plain cement concrete of M10 grade using 20 mm and down size coarse graded hard stone aggregate for levelling course in foundation at any mass concrete and other similar works at all levels and heights, elevations, mechanical controlled mixing, transporting and placing, pumping at all lifts, vibrating, compacting, levelling, curing, shuttering, dewatering wherever necessary, the cost of all materials, labour, leads and lifts, tools and plant, machineries etc., complete as per specifications.	995428	17	M3	6,140.70	18%	18,790.54	1,04,391.90
5		Providing and laying in situ cement concrete of trap metal for R.C.C. (M - 25) work in foundations of R.C.C. columns and steel stanchions including dewatering, formwork, compaction finishing and curing etc. complete.(excluding reinforcement and structural steel) Floor and Columns	995428	92	M3	8,528.40	18%	1,41,230.30	7,84,612.80
6		Concrete floor Finishing with Power trowel Machine and Cutting work and providing Polisulphide sealant	995428	320	M2	213.30	18%	12,286.08	68,256.00

7		Providing and fabricating TMT/ twisted bars all diameters for reinforcement in RCC Column works as per requirement and given 150mm spacing inclusive of binding wire, transporting to the site from the stores, straightening, cleaning, cutting, bending to shapes and lengths as per details & placing in position with binding wires at all levells	995428	5350	KGS	106.20	18%	1,02,270.60	5,68,170.00
8		Back filling the excavated earth with Sand in trenches, sides of foundations & basement by watering and ramming including all operational, incidental, labour charges, hire charges of T&P etc complete including cost and conveyance of material and watering charges etc complete for finished item of the work	995428	45	M3	1,698.30	18%	13,756.23	76,423.50
9		Providing II class B.B. masonry (8 inch)with conventional / I.S. type Bricks in C.M. 1:5in superstructure including striking joints, facing out, joints, watering and scaffolding etc. complete. NGL To 2 Mtr Height	995428	275	M2	2,639.70	18%	1,30,665.15	7,25,917.50
10		Plastering and Surface Treatment 18mm thick with mix ratio of 1:6, on both side of Block work.	995428	475	M2	670.50	18%	57,327.75	3,18,487.50
11		Providing and Fixing of Foundation Bolt having size 25 MM to 16 Dia with MS Base Plate 16 MM Thickness	995428	80	Nos	1,046.70	18%	15,072.48	83,736.00

Total Amount Before Tax(Rs) :	28,61,120.70
GST Value :	5,15,001.73
Po Value (Rs) :	**33,76,122.43**

Total Amount in Words: **Thirty three lakhs seventy six thousand one hundred and twenty two only**

B.N.

Prepared By
Arunkumar B N
Consultant

B.N.

Verified By
Arunkumar B N
Consultant

16/3.

Approved By
Jayakishore L
AVP Operations

Terms and Conditions:

1. Warranty 1 year for the items supplied
2. All the items should supply with specific brand mentioned in the quote
3. Items must be deliver on time as specified in the Po

Billing to:
NUCLEUS SATELLITE COMMUNICATIONS (MADRAS) PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

Shipping to:
NUCLEUS SATELLITE COMMUNICATIONS (MADRAS) PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

B.N.

Prepared By
Arunkumar B N
Consultant

B.N.

Verified By
Arunkumar B N
Consultant

16/3

Approved By
Jayakishore L
AVP Operations