CHINTALAPATI HOLDINGS PVT LTD
18, BLG3, ILABSCENTRE
SOFTWAREUNITSLAYOUT,MADHAPUR,
Ranga Reddy, Telangana, 500081

Purchase Order

Supplier Code :
Supplier Name and Address:

SRILA INFRA

House No: 78-15-18/12, Flat No FF1, Srinilaya Apartments,
Syamala Nagar, Revenue Ward No: 31, Rajahmundry,
Andhrapradesh - 533103, INDIA
Email:
GST:

PO Number : **PO/25-26/0003**
PO Date : **16-02-2026**

Payment terms : **50% advance of PO Value along with (PO)**
:**45% on completion of Laying Spun Pipes**
:**5% on completion of work**

Delivery time : Work completion45 days from PO receipt date
Mode of Transport: NA
Incoterms : NA

GST : **36AABCC5085D1ZV**

Please supply the following materials subject to terms and conditions. Kindly acknowledge receipt of this order

Sl.No	Item Code	Description	HSN/SAC code	Qty	UOM	Unit price (Rs)	GST%		Amount in (Rs)
							Rate	Amount	
		Laying of Storm water Drains **(Total Length of Drain considered - 900 RMT)** **BILL OF QUANTITIES FOR STORM WATER DRAINS** **A.EARTH WORK**							
A1		Earth work excavation by manually/mechanical means for Spun Pipeline laying and Manholes etc and depositing the earth on bank with an initial lead of 50m and initial lift of 2.00m in all types of soils up to Soft Disintegrated Rock (SDR) like loamy, and clayey soils like black cotton soils, red earth, ordinary gravel soils, mixture of gravel and S.D.R like shales, ordinary gravel stony earth and earth mixed with fair sized boulders, under water, liquid mud etc. including shoring, strutting,pumping, dewatering, dressing compacting, machinery hire charges,seignoarges charges, etc., including all incidental, operational and labour charges, all tools and plants, watering etc. complete for finished item of work. Including disposing of surplus earth within site premises for all leads and lifts, as directed by the engineer in charge	9954	200	Cum	225	18%	8,100	45,000
A2		Levelling of Excavated soil to acheive 1:300 slope for laying the spun pipeline, Compactting the soil Earth work excavation by manually/mechanical means for foundations, sumps,machine fdn,trenches etc and depositing the earth on bank with an initial lead of 50m in all types of soils up to a depth of 2.0m to 4.0m lvl in Soft Disintegrated Rock (SDR) like loamy, and clayey soils like black cotton soils, red earth, ordinary gravel soils, mixture of gravel and S.D.R like shales, ordinary gravel stony earth and earth mixed with fair sized boulders, under water, liquid mud etc including shoring, strutting, pumping, dewatering, dressing compacting, machinery hire charges, seignoarges charges, etc., including all incidental, operational and labour charges, all tools and plants, watering etc. complete for finished item of work. Including disposing of surplus earth within site premises for all leads and lifts, as directed by the engineer in charge	9954	150	Cum	135	18%	3,645	20,250

A3		Refilling with useful available good excavated earth (including rock) in trenches, sides of foundations and basement in layers not exceeding 15cm thick, including consolidating each deposited layer by power compactors, dressing, watering and ramming upto OMC 95-98% , (proctor density as per morth specifications) including testing 5-6nos at every 400cum in each layers including all operational, incidental, labour charges, hire charges of T & P and machinery, watering, lead and lift charges etc., complete for finished item of work. as directed by the engineer incharge **a) with available excavated soil**	9954	120	Cum	135	18%	2,916	16,200
A4		Supply and laying of 450mm Dia x 2500 mm length spun pipes manufactured accorsing to IS 458: 2003, including taxes unloading and laying using heavy machinery including all operational, incidental, labour charges, hire charges of T & P and machinery, watering, lead and lift charges etc., complete for finished item of work. as directed by the engineer incharge	9954	900	RMT	2,160	18%	3,49,920	19,44,000
A5		Disposal of the Excess soil by mechanical means using tippers machinery etc from Foundations, Debris, etc., towards low lying areas of inside site premises inclusive of all incidental operational labour charges, all loading and unloading, consoildation in layers, Transportation,including all leads, lifts and all Taxes, all types of tools plants and machinery, hire charges of machinery etc., complete for finished item of work. as directed by engineer incharge	9954	80	Cum	90	18%	1,296	7,200
		B.Man holes							
B1		Providing Plain cement concrete in (1:4:8) proportion for foundations and under flooring using 40mm size hard granite metal from approved quarry including cost and conveyance of all materials like cement, sand, coarse aggregate, water to site, including cost of centering and shuttering charges, de-shuttering charges, including seigniorage charges , all incidental,operational and labour charges, all types of taxes, GST,machine mixing, laying compacting, placing and vibrating to required level, all lead and lift charges, all type of tools and plant, hire charges of machinery, water, curing etc., and including cost of cement, complete for finished item of work as directed by engineer incharge		15	Cum	5,400	18%	14,580	81,000
		C.MASONRY WORKS.							
C1		Red Brick masonry walls of any thickness for below plinth, super structure, parapet walls etc., with CM (1:6) prop (Cement:sand) using standard Red brick sizes from approved source having minimum crushing strength of 5 N/sq.mm. including cost and conveyance of all materials like cement, sand, bricks, water etc., seigniorage charges, all incidental and operational, labour charges like mixing cement mortar, scaffolding charges, lift charges, curing etc., of all heights complete for finished item of work.		65	Cum	9,000	18%	1,05,300	5,85,000

		D.PLASTERING WORKS							
D1		Providing impervious coat to exposed Massonry walls surfaces to required slopes with CM (1:5) prop. 20mm thick mixing with water proofing compound of approved compound from reputed manufacturers like FOSROC or SIKA or Dr. Fixit, including cost and conveyance of materials like cement, sand, water proofing compound etc., to site, seigniorage charges and labour charges rendering smooth , curing lift charges etc., complete but including cost of Cement, for finished item of		300	Sqm	450	18%	24,300	1,35,000
		E.MISCELANEOUS WORKS							
E1		Supplying & Providing 50 mm thk FRPManhole covers of capacity 5MT including cost and conveyance of all materials like cement, sand, water etc to site, cost of seigniorage charges and all other taxes, GST, on all materials, and including all operational, incidental charges and labour charges for mixing mortar, finishing, fixing in position, scaffolding,Form work, lift charges, curing, Complete finished item of work as per Drawing and as directed by Engineer - in - charge .		30	Nos	2,700	18%	14,580	81,000
		F.HARVESTING PITS							
F1		Water harvesting pits as per drawing with one layer river sand,one layer with 20mm metal layer and last layer with 40mm metal each of required thickness including excavtion of soil and disposing surplus earth within sit premisis as directed by the engineer incharge		8	Nos	22,500	18%	32,400	1,80,000
F2		Providing and fixing factory made precast RCC perforated drain covers, having concrete of strength not less than M-25, of size 1000 x 450x50 mm, reinforced with 8 mm dia four nos longitudinal & 9 nos cross sectional T.M.T. hoop bars, including providing 50 mm dia perforations @ 100 to 125 mm c/c, including providing edge binding with M.S. flats of size 50 mm mm x 1.6 mm complete, all as per direction of Engineer-in-charge.		7.65	Sqm	1,800	18%	2,479	13,770

Total Amount Before Tax(Rs) :	31,08,420
GST Value :	5,59,516
Po Value (Rs) :	**36,67,936**

Total Amount in Words: **Thirty Six lakhs Sixty Seven thousand and nine hundred and thirty six only**

Prepared By	Verified By	Approved By
Arunkumar B N	Jayakishore L	Sudharsan M
Consultant	AVP Operations	COO

Terms and Conditions:

Start of work:
Once the supplier receipt of PO acceptance has to be made within 24 hrs and start of work to be carried out immediately (within 1-2 days)

Delivery & Execution:
Supplier has to complete the work on or before 45 days from receipt of PO. PO receipt must be acknowledged through electronic mail. Work should be carried out as per work schedule given by the supplier. Supplier exceeds the time line of completion may leads to LD clause as per Industry standards

Specification and changes:
No changes should be made against the scope if any necessity changes to be made during the execution should be discussed and agreed with customer without affecting the completing date and should the incorporate within the Po prices

Cancellation:
Once the supplier agreed and acknowledge the PO which cannot be cancelled during the execution time by the supplier at any cause. Acceptance criteria must includes consideration of all factors.

Inspection of product:
Brand/make of materials to be supplied and used for the scope of work should be Honer as per the PO. Deviations shall not be accepted and rejected by the customer moreover it should not make any loss of time interms of reprocurement and rework.

Warrenty:
Supplier should pass on the warranty of the raw materials and warranty of work. Warranty period of 5-7 years from the date of installation includes any damages, distortion and dismantling of any element due to the natural climatic conditions.

LD Clause:
The supplier agrees that the Late Delivery/Execution for the delayed work @2% of work order for every week and maximum of 8-10% upto 1 month shall be paid to Buyer

Billing to:
CHINTALAPATI HOLDINGS PVT LTD
18, BLG3, ILABSCENTRE
SOFTWAREUNITSLAYOUT,MADHAPUR,
Ranga Reddy, Telangana, 500081

Shipping to:
NUCLEUS SATELLITE COMMUNICATIONS (MADRAS) PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

Prepared By	Verified By	Approved By
Arunkumar B N	Jayakishore L	Sudharsan M
Consultant	AVP Operations	COO