VAT TECH ENGINEERING PVT LTD NO: 38 KARPAGAMPAL NAGAR NANDHIVARAM GUDUVANCHERI GSTIN/UIN: 33AAECV6181C1ZI State Name : Tamil Nadu, Code : 33	Voucher No. 45	Dated 25-Mar-26
		Mode/Terms of Payment 30% Advance with PO
	Buyer's Ref./Order No. 45	Other References PO/25-26/0114 dt 19-03-
Buyer (Bill to) YANVIOR TECHNOLOGIES PVT LTD 465,CITRUS DRIVE MOPURU PALLI VILLAGE, SATHYAVEDU Sri City,Tirupati Andhra Pradesh-517541 GSTIN/UIN : 37AAACN9960D2ZA State Name : Andhra Pradesh, Code : 37	Dispatched through	Destination
	Terms of Delivery	

Sl No	Description of Goods and Services	HSN/SAC	Quantity	Rate	per	Amount
C	Installation charges					
1	**Outdoor unit installation charges**	995463	2 No	6,210.00	No	12,420.00
2	**Installation charges for VRV Indoor units.**	995463	12 No	3,105.00	No	37,260.00
D	**Installation charges for Floor Mounted type Air Handling Unit**					
1	**Soft/Hard drawn Refrigerant Copper piping** *between Indoor & Outdoor units covered with suitable Nitrile Rubber Insulation 13/19 mm thick .*	995463	100 RMT	1,966.50	RMT	1,96,650.00
E	***Control Cabling***					
1	**2 core 1.0 Sq.mm flexible control cable & PVC** *conduits to connect outdoor units.*	995463	150 RMT	134.10	RMT	20,115.00
F	*PVC drain piping with supports, clamps and 6mm thick Nitrile rubber tube insulation of following*					
1	**32 mm dia**	995463	80 RMT	248.40	RMT	19,872.00
2	**R-410A Gas.**	995463	25 kgs	931.50	kgs	23,287.50
3	**Indoor Unit Necessary Y Joints**	995463	11 No	310.50	No	3,415.50
4	**Outdoor Unit Necessary Y Joints**	995463	1 No	621.00	No	621.00
5	**Unit lifting shifting , positioning Vaccumeising ,** *Pressure testing and Commissioning charges*	995463	36 HP	1,035.00	HP	37,260.00
6	**Cassette Indoor Unit supporting from roof** *threaded rod,nut & washer etc (structural support by Client)*	995463	12 No	1,035.00	No	12,420.00
7	**Copper pipe supporting from roof threaded** *rod,nut & washer etc (structural support by Client).*	995463	1 lot	6,210.00	lot	6,210.00
8	**Outdoor Unit MS stand stool type**	995463	2 No	8,280.00	No	16,560.00
9	**Civil work for Outdoor unit Leg**	995463	2 No	2,070.00	No	4,140.00
G	**CABLE / PIPE TRAYS : Supply & Installation of pre-galvanized sheet steel perforated cable tray along with top cover. The cable tray shall include necessary supports and other accessories.**					
1	**200mm wide x 100 mm height only outside** *building*	995461	15 RMT	879.30	RM	13,189.50
2	**Scafholding arrangement for internal works**	997319	1 lot	12,420.00	lot	12,420.00
3	**Supply & Installation of MS Supports for VRV IDU**	995463	300 Kg	186.30	kgs	55,890.00

	ETC					
4	**Transport Charges (Lot)**	996511	1 lot	10,350.00	lot	**10,350.00**
						4,82,080.50
	OUTPUT IGST18%			*18*	%	**86,774.49**
	Total					**Rs 568854.99**

Amount Chargeable (in words) *E. & O.E*

INR Five Lakh sixty eight Thousand eight Hundred fifty four and ninty nine paise Only

Company's PAN **AAECV6181C**

for VAT TECH ENGINEERING PVT LTD

SRINIVASAN CHELLAN
Digitally signed on
07-04-2026 11:28:47

Authorised Signatory