CHINTALAPATI HOLDINGS PVT LTD
18, BLG3, ILABSCENTRE
SOFTWAREUNITSLAYOUT,MADHAPUR,
Ranga Reddy, Telangana, 500081

Purchase Order

Supplier Code :
Supplier Name and Address:

SRILA INFRA

House No: 78-15-18/12, Flat No FF1, Srinilaya Apartments,
Syamala Nagar, Revenue Ward No: 31, Rajahmundry,
Andhrapradesh - 533103, INDIA
Email:
GST:

PO Number : **PO/25-26/0004**
PO Date : **16-02-2026**
Payment terms : **50% advance of PO Value along with (PO)**
:**45% on completion of Kerb Stones Work**
:**5% on completion of work**
Delivery time : Work completion 45 days from PO receipt date
Mode of Transport: NA
Incoterms : NA

GST : **36AABCC5085D1ZV**

Please supply the following materials subject to terms and conditions. Kindly acknowledge receipt of this order

Sl.No	Item Code	Description	HSN/SAC code	Qty	UOM	Unit price (Rs)	GST%		Amount in (Rs)
							Rate	Amount	
		SIDEWALK **(Total Area of Footpath considered - 900 Sqm)** **BILL OF QUANTITIES** **A.EARTH WORK**							
A1		Earth work excavation by manually/mechanical means for laying Kerbstones and Manholes etc and depositing the earth on bank with an initial lead of 50m and initial lift of 2.00m in all types of soils up to Soft Disintegrated Rock (SDR) like loamy, and clayey soils like black cotton soils, red earth, ordinary gravel soils, mixture of gravel and S.D.R like shales, ordinary gravel stony earth and earth mixed with fair sized boulders, under water, liquid mud etc. including shoring,strutting, pumping, dewatering, dressing compacting, machinery hire charges, seignoarges charges, etc., including all incidental,operational and labour charges, all tools and plants, watering etc.complete for finished item of work. Including disposing of surplus earth within site premises for all leads and lifts, as directed by the engineer in charge	9954	324	Cum	350	18%	20,412	1,13,400
A2		Supply installation of KerbStones of Size 450mm x 450mm x 100mm manufactured as per IS 5758:2020, including taxes unloading and laying using machinery including all operational, incidental, labour charges, hire charges of T & P and machinery, watering, lead and lift charges etc., complete for finished item of work. as directed by the engineer incharge	9954	1,805	RMT	850	18%	2,76,165	15,34,250
A3		Refilling with useful available good excavated earth (including rock) in trenches, sides of foundations and basement in layers not exceeding 15cm thick, including consolidating each deposited layer by power compactors, dressing, watering and ramming upto OMC 95-98% , (proctor density as per morth specifications) including testing 5-6nos at every 400cum in each layers including all operational, incidental, labour charges, hire charges of T & P and machinery, watering, lead and lift charges etc., complete for finished item of work. as directed by the engineer incharge **a) with available excavated soil**	9954	450	Cum	150	18%	12,150	67,500

A4		Supply and laying of 200mm x 200mm x 60mm and 200mm x 100mmx 60mm M35 Grade Pavers manufactured according to IS 15658:2021, including taxes unloading and laying using machinery including all operational, incidental, labour charges, hire charges of T & P and machinery, watering, lead and lift charges etc., complete for finished item of work. as directed by the engineer incharge	9954	900	Sqm	1,000	18%	1,62,000	9,00,000
A5		Painting of KerbStones	9954	350	Sqm	250	18%	15,750	87,500

Total Amount Before Tax(Rs) :	27,02,650
GST Value :	4,86,477
Po Value (Rs) :	**31,89,127**

Total Amount in Words: **Fifty three lakhs Nineteen thousand and two hundred and ninety three only**

Prepared By	Verified By	Approved By
Arunkumar B N	Jayakishore L	Sudharsan M
Consultant	AVP Operations	COO

Terms and Conditions:

Start of work:
Once the supplier receipt of PO acceptance has to be made within 24 hrs and start of work to be carried out immediately (within 1-2 days)

Delivery & Execution:
Supplier has to complete the work on or before 45 days from receipt of PO. PO receipt must be acknowledged through electronic mail. Work should be carried out as per work schedule given by the supplier. Supplier exceeds the time line of completion may leads to LD clause as per Industry standards

Specification and changes:
No changes should be made against the scope if any necessity changes to be made during the execution should be discussed and agreed with customer without affecting the completing date and should the incorporate within the Po prices

Cancellation:
Once the supplier agreed and acknowledge the PO which cannot be cancelled during the execution time by the supplier at any cause. Acceptance criteria must includes consideration of all factors.

Inspection of product:
Brand/make of materials to be supplied and used for the scope of work should be Honer as per the PO. Deviations shall not be accepted and rejected by the customer moreover it should not make any loss of time interms of reprocurement and rework.

Warrenty:
Supplier should pass on the warranty of the raw materials and warranty of work. Warranty period of 5-7 years from the date of installation includes any damages, distortion and dismantling of any element due to the natural climatic conditions.

LD Clause:
The supplier agrees that the Late Delivery/Execution for the delayed work @2% of work order for every week and maximum of 8-10% upto 1 month shall be paid to Buyer

Billing to:
CHINTALAPATI HOLDINGS PVT LTD
18, BLG3, ILABSCENTRE
SOFTWAREUNITSLAYOUT,MADHAPUR,
Ranga Reddy, Telangana, 500081

Shipping to:
NUCLEUS SATELLITE COMMUNICATIONS (MADRAS) PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

Prepared By	Verified By	Approved By
Arunkumar B N	Jayakishore L	Sudharsan M
Consultant	AVP Operations	COO