NUCLEUS SATELLITE COMMUNICATIONS (MADRAS) PVT LTD

465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

Purchase Order

Supplier Code :
Supplier Name and Address:

AGNI AGRITECH PRIVATE LIMITED

PLOT NO 18 BUILDING NO 3,
ILABS CENTER,SOFTWARE UNITS LAYOUT
Madhapur,Hyderabad,Telangana-500081
Email:
GST: 36ABBCA7594C1ZN

PO Number : **PO/25-26/084**
PO Date : **17-02-2026**
Payment terms : **30% Advance remaining against billing**
Delivery time : **Within 4-8 Weeks**
Mode of Transport: **Road**
Incoterms : **Deliver to Sricity**
GST : **37AAACN9960D2ZA**

Please supply the following materials subject to terms and conditions. Kindly acknowledge receipt of this order

Sl.No	Item Code	Description	HSN/SAC cod	Qty	UOM	Unit price (Rs)	GST%		Amount in (Rs)
							Rate	Amount	
		FIRE FIGHTING SYSTEM (Hydrant System)							
		ANNEXURE A - FIRE PUMP ROOM EQUIPMENTS							
1		Supply, installing, testing, & commissioning of Electric motor driven Main Pump suitable for automatic operation consisting of the following (as per specification). Horizontal, End suction, Top Discharge Centrifugal pump of bronze fitted construction with bronze impeller with SS.STEEL SHAFT with Gland Packing coupled to KIRLOSKAR make squirrel cage, totally enclosed fan cooled, horizontal foot mounted, continuous rated, AC 3 Phase, 415 Volts, 50Hz ±5%, combined variation ±10% motor, S1 duty, 50° C ambient, class F Insulation, IP-55 Protection both mounted on a common base plate with standard Love joy coupling, MS coupling guard for delivery of 171 m3/hr against a total head of 70 metres.		1	Nos	4,26,624.00	18%	76,792.32	4,26,624.00
2		Motor driven jockey pump , horizontal centrifugal end suction back pull out/horizontal centrifugal mulit-stage ,10.8LPM @ 70MWC, CI -IS210 Gr FG260 casing, IS318-LTB2 bronze impeller,shaft sleeve and casing ring, Carbon Steel / SS shaft, gland packed as per IS5120, painted fire red,coupling/coupling guard, base plate, matching flanges, alignment, grouting, etc complete, the pump characteristic curve shall be continuously rising towards shut off and shut off head shall be at least 5% higher than duty point and not more than 20% of duty point,-make KBL/M&P. motor sq cage, 3ph, 4 wire, neutral grounded, 415V+/-10%,50Hz		1	Nos	1,30,653.60	18%	23,517.65	1,30,653.60
3		Supply, Erection, Testing and Commissioning of Diesel engine driven horizontal end suction centrifugal pumpset with bronze impeller, cast iron body rated 171 Cu.m/hr at 70 MWC 2150 RPM complete with Diesel engine, common baseframe, etc.,		1	Nos	6,07,050.40	18%	1,09,269.07	6,07,050.40
4		Supply and erection of Diesel engine pannel with auto starter pressur switch cables etc,		1	Nos	37,329.60	18%	6,719.33	37,329.60
5		Providing & fixing , testing & commissioning of cubical type floor mounted Control / Starter Panel for Fire Pumps fabricated FROM 16G M.S sheet dully painted with stove enamelled finish of approved shade and comprising of all Incomers ,MCCB Switch Unit, Isolation MCCB Switch unit of Suitable Capacity for each Pump, Fully Automatic Star Delta Starter for each Electric Pump, Over load relays,ndicating Lamps, Panel type Ammeter & Voltmeters. The Panel shall be complete in all respect to make the Fire Hydrant and sprinkler system fully Functional.		1	Nos	3,82,184.00	18%	68,793.12	3,82,184.00

6		Supply and erection of Engine exuast glass wool and aluminiyam clading		10	Mtrs	5,332.80	18%	9,599.04	53,328.00
7		Supply and Laying of following size of cable in cable tray i/c. providing and making cable terminations by crimping joints as reqd for interconnecting the equipments/motors as reqd at site complete as reqd.							
		3½ Core 95 Sqmm XLPE Alu. Ar. Cable		25	Mtrs	297.75	18%	1,339.87	7,443.70
		4 Core 25 Sqmm XLPE Alu. Ar. Cable		25	Mtrs	244.42	18%	1,099.89	6,110.50
		4 Core 10 Sqmm XLPE Cu. Ar. Cable		25	Mtrs	191.09	18%	859.91	4,777.30
		2 core X1.5Sq.mm PVC copper armoured cable		100	Mtrs	105.77	18%	1,903.81	10,576.72
		12 core X 1.5 Sq.mm PVC copper armoured cable		25	Mtrs	222.20	18%	999.90	5,555.00
		3½ Core 95 Sqmm XLPE Alu. Ar. Cable		2	Nos	1,217.66	18%	438.36	2,435.31
		4 Core 25 Sqmm XLPE Alu. Ar. Cable		4	Nos	844.36	18%	607.94	3,377.44
		4 Core 10 Sqmm XLPE Cu. Ar. Cable		2	Nos	745.70	18%	268.45	1,491.41
		12 core X 1.5 Sq.mm PVC copper armoured cable		2	Nos	571.50	18%	205.74	1,143.00
		Earthing 50mm GI pipe with funnel 50x6mm GI flat, digging and earth manual.		2	Nos	18,220.40	18%	6,559.34	36,440.80
		single core copper 25sqmm yellow green		20	Mtrs	266.64	18%	959.90	5,332.80
		GI Earth Flat 50 x6mm		100	Mtrs	213.31	18%	3,839.62	21,331.20
8		Supply, installing, testing and commissioning GI Cable Tray of following sizes,							
		150mm GI Cable Tray		35	Mtrs	393.74	18%	2,480.55	13,780.84
		100mm GI Cable Tray		35	Mtrs	297.75	18%	1,875.81	10,421.18
		50mm GI Cable Tray		20	Mtrs	235.53	18%	847.92	4,710.64
9		Supply, Installation, Testing and Commissioning of MS pipes of C class, ERW, as per IS:1239 & IS:3589 Part-I with necessary fittings							
		250mm dia		12	Mtrs	4,128.48	18%	8,917.51	49,541.71
		200 mm dia		18	Mtrs	3,341.89	18%	10,827.72	60,153.98
		150 mm dia		18	Mtrs	2,479.75	18%	8,034.40	44,635.54
		65mm dia		12	Mtrs	924.35	18%	1,996.60	11,092.22
		80 mm dia		18	Mtrs	1,128.78	18%	3,657.23	20,317.97
		40mm dia		130	Mtrs	782.14	18%	18,302.17	1,01,678.72
		32mm dia		90	Mtrs	595.50	18%	9,647.04	53,594.64
		25 mm dia		280	Mtrs	471.06	18%	23,741.63	1,31,897.92
10		Supply, Installation, Testing and Commissioning of Non Return Valve of PN 16 pressure rating complete with matching flanges ANSI class # 150 ,with bolts & nuts etc. Wafer Plate Type							
		150mm		2	Nos	11,198.88	18%	4,031.60	22,397.76
		65 mm		1	Nos	6,754.88	18%	1,215.88	6,754.88
11		Supply, Installation, Testing and Commissioning of Y stainer of PN 16 pressure rating complete with matching flanges ANSI class # 150 ,with bolts & nuts etc.							
		200mm		2	Nos	45,862.08	18%	16,510.35	91,724.16
		80 mm		1	Nos	14,842.96	18%	2,671.73	14,842.96
12		Supply, Installation, Testing and Commissioning of Butter fly valve of PN 16 pressure rating complete with matching flanges ANSI class # 150 ,with bolts & nuts etc.							
		250mm(Gear operator type)		2	Nos	28,441.60	18%	10,238.98	56,883.20
		200mm(Gear operator Type)		2	Nos	18,042.64	18%	6,495.35	36,085.28
		150 mm		4	Nos	10,932.24	18%	7,871.21	43,728.96
		65 mm		1	Nos	9,510.16	18%	1,711.83	9,510.16
13		Supply & Erection of 25 NB Gun Metal Ball valve for vent, test & drain valve		8	Nos	1,990.91	18%	2,866.91	15,927.30
14		Supply Installation testing and commissioning of Ms Pressure Gauge with necessary fittings 0 to 16 100mm dia		5	Nos	1,990.91	18%	1,791.82	9,954.56
15		Supply, installation testing and commissioning of Pressure Swith with ball valve nessary fittings		3	Nos	4,399.56	18%	2,375.76	13,198.68

16		Supply, Installation, Testing and Commissioning of air release valve		2	No	3,155.24	18%	1,135.89	6,310.48
17		Supply, erection, testing and commissioning of Air cushion tank of 200 mm dia. & 1200 mm hight with drain connection. The rate shall be inclusive of 25mm dia Air release valve and ball value Pressure relif valve		1	Nos	35,107.60	18%	6,319.37	35,107.60
18		Supply erection testing and commssioning of 100mm mainy folding for presser switches and pressure guges settup system		1	Nos	4,177.36	18%	751.92	4,177.36
19		Supply and erection of pump room all fittings reducrs elbows matching flanges gasket bolt nut tee,s clamps couplings nipples etc		1	lot	24,886.40	18%	4,479.55	24,886.40
20		Supply and erection of Diesel tank and valves all fittings reducrs elbows matching flanges gasket bolt nut tee,s clamps couplings nipples etc		1	lot	37,774.00	18%	6,799.32	37,774.00
21		Supply, Installation, Testing and Commissioning of Structural Support materials for pipes supports		1500	Kgs	127.10	18%	34,316.57	1,90,647.60
22		Civil- pedestal work for hydrant pipe laying 600x300x450mm pcc 450,Rcc 600x300		130	Nos	3,555.20	18%	83,191.68	4,62,176.00
23		Sprinkler for office area and canteen							
24		Supply and Erection of 1500 Mm flixable drop		100	Nos	2,577.52	18%	46,395.36	2,57,752.00
25		Supply and errection of sprinkler K-Factor 68 degree		100	Nos	453.29	18%	8,159.18	45,328.80
26		Supply errction of rosser plate		100	Nos	248.86	18%	4,479.55	24,886.40
		ANNEXURE C - External and Internal Hydrant							
1		Supply, Installation, Testing and Commissioning of underground laying of MS pipes of C class, ERW, as per IS:1239 & IS:3589 Part-I with clamps and necessary fittings							
		150 mm dia		700	Mtrs	2,479.75	18%	3,12,448.75	17,35,826.40
		80 mm dia		78	Mtrs	1,279.87	18%	17,969.40	99,830.02
		25 mm dia		18	Mtrs	471.06	18%	1,526.25	8,479.15
2		Supply, Installation, Testing and Commissioning of Butterfly Valve of PN 16 pressure rating complete with matching flanges ANSI class # 150 ,with bolts & nuts etc.							
		150 MM		5	Nos	10,932.24	18%	9,839.02	54,661.20
3		Supply, Installation, Testing and Commissioning of 4 way Fire Brigade inlets SS with Butterfly Valve to the fire fighting water tank and fire service vehicles as per Local fire service department's requirement. & Butterfly Valve 150mm dia		1	Nos	23,997.60	18%	4,319.57	23,997.60
4		Supply, Installation, Testing and Commissioning of Oblique pattern single headed 63 mm diameter SS hydrant valve with female type instantaneous outlet including flanged inlet & drilling and valve and as per spec for internal &external hydrants with blank cap with chain with all accessories-ISI		20	Nos	6,043.84	18%	21,757.82	1,20,876.80
5		Supply, Installation, Testing and Commissioning of M.S. CRCA sheet fabricated 18 SWG Fire Hydrant hose boxes suitable for storing 2 Nos. 15M hoses and 1 No. SS branch pipe with Nozzle of 63mm dia size. Boxes will be duly painted with two coats each of red oxide primer and finish enamel fire red colour outside & white inside with locking arragement for double leaf front glass doors having 4mm thick glass, complete as per specifications.ISI		20	Nos	4,488.44	18%	16,158.38	89,768.80

6		Supply, Installation, Testing and Commissioning of SS Fire Hoses of RRL Hose with 63 mm diameter type 15 Mtrs fire hose to IS:8423, with female and male instantaneous SS coupling on either ends		40	Nos	4,532.88	18%	32,636.74	1,81,315.20
7		Supply, Installation, Testing and Commissioning of SS short branch pipe nozzle 63 X 19mm dia size as per IS:903,-ISI		20	Nos	2,133.12	18%	7,679.23	42,662.40
8		Supply and instalation testing and commissioning of Hose reel drumm30mtr lenth		20	Nos	6,443.80	18%	23,197.68	1,28,876.00
9		Supply and erection of Air release valve with ball valve		2	Nos	3,848.50	18%	1,385.46	7,697.01
10		Supply and erection of pressure release valve with ball valve		2	Nos	4,310.68	18%	1,551.84	8,621.36
		Supply Installation testing and commissioning of Ms Pressure Gauge with necessary fittings 0 to 16 100mm dia		2	Nos	1,990.91	18%	716.73	3,981.82
11		Supply and erection of Ms-Support with one coat primer two coat painting		1800	Kg	127.10	18%	41,179.88	2,28,777.12
12		Hume pipe for underground 450x450mm dia		30	Mtrs	2,933.04	18%	15,838.42	87,991.20
13		Wrapping coat for uder ground pipes		42	Mtrs	1,777.60	18%	13,438.66	74,659.20
14		FRP Ready Made tank 1.5KL		1	Nos	12,79,872.00	18%	2,30,376.96	12,79,872.00
		FIRE EXTINGUISHER							
1		CO2 4.5KG		15	Nos	5,243.92	18%	14,158.58	78,658.80
2		ABC 6KG stored pressure Fire Extinguisher		15	Nos	3,199.68	18%	8,639.14	47,995.20

Total Amount Before Tax(Rs) :	79,59,612
GST Value :	14,32,730
Po Value (Rs) :	**93,92,342**

Total Amount in Words**: Ninety Three Lakhs Ninety Two thousand Three Hundred and Forty Two only**

B. N.

Jayakishore. L

Prepared By | Verified By | Approved By

Terms and Conditions:

*Technical Specifications & Item wise prices are attached as per Annexures. All Annexures are need to be duly signed and stamped

*General terms & conditions of the PO is attached to be duly signed and stamped.

1.Deposits & Retention Money: Retention Money: An Amount equal to 5% of the value of the Bill shall be recovered from each Running Bill and retained with the Owner without any interest. This shall be refunded after the expiry of the Defect Liability Period and submission of proof of payment of all taxes, Royalties, seiner age charges, Cess etc.

2.Payment of Running Bills: The payment will be released in the form of running bills duly approved by Engineer in charge in according's with actual progress of work and measurements recorded in MBook at site within 30 Days from Approval of Engineer In Charge Or Submission of Bill whichever is later by Buyer.

3. Delivery /Execution: Within 35 DAYS from the receipt of PO

4.Defect Liability Period: 35 Days from successful handing over of the complete Project.

5.Taxes: The Quoted rates of the Contractor shall be inclusive of all Taxes, Duties, Royalties, Seino rage Charges, Entry Taxes, Excise, Purchase Tax Work Contract Tax, etc., at the prevailing Tariffs. Tax at source like Income Tax, Works contract taxes, GST as applicable shall be deducted on all bills &appropriate certificates shall be given. GST and Labour cess shall be paid Extra Enhancement of Tax Tariffs if any during the execution period shall be to the account of the Contractor only. No claim for the enhancement of Taxes shall be entertained.

6. L.D. Clause: A Penalty of 0.5% of the Contract Value shall be imposed as L.D. and not as Penalty for the delay of every week beyond the stipulated period subject to a maximum of 5% of the total contract value.

7. Insurance : C.A.R. Insurance Policy covering the works and workers compensation shall be taken by the Contractor, Validity extending to the end of Defect Liability Period.

8. Water & Power: Water Supply - Owner Scope Water Distribution system - Contractor scope

Power Consumption shall be charged at the prevailing Tariffs (Commercial) to the extent of Consumption on the works.

9. Authority of the Owner : The Owner reserves the right to add/delete the items mentioned in the BOQ, subsequently the final PO Value / bill may vary.

10. Quoted Rates: The Quoted rates shall be maintained firm till the completion of the project works. No escalation shall be considered due to increase in rates of materials or labour etc.,

12. All disputes subject to Tirupati court jurisdiction.

A. General:

1.We do not accept any responsibility for any order unless issued on our official signed purchase order form.

2. Buyer may terminate or cancel work under this order in whole or in part at any time by written or telegraphic notice. Termination shall be without prejudice to any claims which one party may have against the other for work performed and materials supplied up to date of cancellation.

3. The supplier guarantees that the sale or use of the products supplied by him will not infringe any Indian or foreign patent, design or trade mark and undertaken to indemnify and keep us indemnified against any actions, judgments, decrees, costs, claims, demands and expenses resulting from any actual or alleged infringement. The supplier further undertakes at his own expense to defend or assist in the defence of any suit or action which may be brought on us in this connection.

4. Should the supplier quote or offer better terms to any other party for any material of similar specification and quantity, we shall have the option to purchase on the same terms. The benefit of such reductions is to be with retrospective effect of the lower price whichever is earlier.

5. Goods rejected for any reason in terms of this contract will remain at our premises at supplier's risk and cost. The supplier will have to remove the rejected material if supplied locally, within three days of our limitation and /or receipt of the rejection memo, and for goods supplied from outstation, we would give notice for removal disposal by the supplier within seven days. Rejected goods bearing our trademark or emblems etc. will no be returned to the supplier and will be destroyed at supplier's cost at our end to avoid misuse. No cost shall be provided in this regard.

6. Any terms and conditions rescinding, adding to or altering the terms of this purchase order subsequently shall always be in writing by amendment order. All such additions, alterations or deletions as per amendment order shall be deemed to be incorporated herein and made part of this purchase order.

7. In the event of any breach of this contract on the part of the supplier, the supplier agrees to compensate us in such a manner, as may be determined by us.

8.The enclosed copy of this order must be duly signed by the vendor and returned to us with 3 days, failing which this order will be deemed to have been accepted.

9. We reserves the right to cancel Purchase order or Work order issued if order acknowledgement is not received in 3 days.

10. Purchase orders sent by mail to suppliers will be deemed to have been accepted in too, unless objection if any are received by us by return mail within 48 hours of our transmission.

B. Laws &Regulations: Seller warrants that all commodities delivered pursuant to this order will have produced, sold and delivered to Buyer in compliance with all applicable Central, State Municipal etc., laws and regulations.
C. Jurisdiction: In the event of any dispute arising out of the order/contract only the courts in Tirupati will have jurisdiction.
D. Patents: Seller will exonerate indemnity and hold harmless the buyer from and against any and all liability damage. cost or expense which may accrue to or be sustained by Buyer on account of any claim, suit or action make or threatened to be brought against. Buyer or its customer for actual or alleged infringement of any patent, by reason of the manufacture of goods covered by this order by seller the resale thereof by Buyer or use of said goods or any part thereof for a purpose known to Seller and Seller at Buyer's request will defend at Seller's expense, any such claim, suit or action
E. Warranties: The Seller warrants supplies when delivered hereunder to be free from all defect of material or workmanship to confirm strictly to the specifications, drawings or samples specified or furnished and to be fit for the use and purposes intended free from all patent and latent defects the breach whereof shall give the Buyer without prejudice to his other rights and remedies and right to reject the supplies and treat the contracts as repudiated. All warranties shall survive any intermediate or final inspections deliver, acceptance, or payment by purchase and shall continue in effect through a period of one year beginning with the date of delivery of supplies to Buyer.
F. Waivers: Any failure by Buyer to enforce or require strict performance by Seller or any terms or conditions of this order shall not constitute a waiver there of Buyer and Buyer may at any time avail himself of the remedies. Buyer may have for any breach of the terms hereof.
G. Force Majeure Conditions: We reserve the right to cancel this purchase order or any part thereof due to fire, strikes, lockout and force majeure or from any other cause or causes beyond our control or from any cause or causes due to acts or demands of the government or as a consequence of war or outbreak of hostilities.
H. Quality Standards:
1. The goods supplied must confirm to our standard specifications or samples as the case may be.
2. If the goods supplied against this order do not confirm to the standard, specifications or samples approved by us the same shall be liable to be rejected at the suppliers cost and risk. Our decision on the question whether the goods supplied confirm to the standards,
specifications or samples approved either directly by us or any third party inspecting agency.
3. The Buyer may at any time by written order, make changes in the drawings, designs or specifications applicable to the supplies covered by this purchase order with.
4.4.All items manufactured by the supplier according to our furnished blueprints, drawings,designs, manufacturing data,, specifications or information shall not be utilized by the supplier

or anyone on his behalf for sale, manufacture or for any other purpose save as agreed by us in writing.
I. Transit Insurance:
The goods are to be insured for transit risk at vendor's expense unless otherwise authorized by us.
J. Packing:
1. All articles shall be suitably packed or otherwise prepared for dispatch by consolidation package, so as to secure the lowest transportation rates and to meet carrier's requirements. No charges will be allowed for packing, carting or cartage unless stated in the order. Each packing must be marked to show quantity, contents name of supplier, any other markings as required which are mandatory. Packing list to be sent along with invoice.
2. Unless otherwise agreed, all materials ordered are to be supplied F.O.R. destination as specified in the purchase order, and no charges for packing, boxing or crating will be accepted unless authorized in the purchase order.
K. Delivery :
1. Delivery time is the essence of the contract and the buyer may reject the goods and services not delivered or furnished on dates herein informed. Delivery must be effected within the time stated. We reserve to ourselves the right to purchase the goods in the open market and charge the supplier with any loss incurred as a result thereof or to cancel the order.
2. Unless otherwise agreed to in writing the weights and measurements at our delivery point will be taken as correct and final. Whenever applicable, we have right to have reweighment either as per weigh bridge / external weight bridge. Tolerance limit of acceptance of shall be strictly as required
3. The buyer shall have the option to cancel or to reject the goods in case of short delivery. Part deliveries will be accepted only if so specified.
L. Documents:
All the documents and correspondence covering the supply of goods should indicate our order no. and date. The delivery challan and bill should be submitted in TRIPLICATE, failing which the deliveries are likely to be refused and payment delayed. Separate DC's are to be made for each partial supply covered by a single invoice. The bill should give reference of the order as well as the delivery challan(s), packing list etc.,
M. Payment Advance:
Payment made for supplies received as per this purchase order prior to inspection shall not constitute as acceptance thereof. In the event of rejection such advance has to be refunded
together with interest unless authorized by us for adjustment against future supplies.

Billing to:
NUCLEUS SATELLITE COMMUNICATIONS (MADRAS) PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

Shipping to:
NUCLEUS SATELLITE COMMUNICATIONS (MADRAS) PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

B. N.

Jayakishore

Prepared By | Verified By | Approved By