YANVIOR TECHNOLOGIES PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

Purchase Order

Supplier Code :
Supplier Name and Address:

Vat Tech Enggineering . Pvt Ltd

No 38, Karpagambal Nagar
Nandhivaram Guduvancherri 603202
Tamilnadu,India
Email:
GST: 33AAECV6181C1ZI

PO Number : **PO/25-26/0115**
PO Date : **19-03-2026**
Payment terms : **30% Advance with PO**
60 % Against delivery of materials at site
10% After testing and commisioning
AC VRF and AHU unit 100% Advance payment
Delivery time : **4 weeks**
Mode of Transport: **Road**
Incoterms : **Deliver to Sricity**
GST : **37AAACN9960D2ZA**

Please supply the following materials subject to terms and conditions. Kindly acknowledge receipt of this order

Sl.No	Item Code	Description	HSN/SAC code	Qty	UOM	Unit price (Rs)	GST%		Amount in (Rs)
							Rate	Amount	
		Mezzanine & GM Office area							
A		**SUPPPLY OF VRF OUTDOOR UNITS**							
1		32HP Outdoor units	84159000	1	Nos	6,27,300.90	18%	1,12,914.2	6,27,300.90
B		**SUPPLY OF VRF INDOOR UNITS/AHU AND ACCESSORIES**							
1		1.5 TR Cassette Indoor unit with front panel and remote control	84159000	1	Nos	43,431.30	18%	7,817.6	43,431.30
2		2.0 TR Cassette Indoor unit with front panel and remote control	84159000	3	Nos	44,451.00	18%	24,003.5	1,33,353.00
3		2.5 TR Cassette Indoor unit with front panel and remote control	84159000	2	Nos	49,009.50	18%	17,643.4	98,019.00
4		3.2 TR Cassette Indoor unit with front panel and remote control	84159000	2	Nos	49,850.10	18%	17,946.0	99,700.20
5		4.0 TR Cassette Indoor unit with front panel and remote control	84159000	2	Nos	50,869.80	18%	18,313.1	1,01,739.60
C		**Installation charges**							
1		Outdoor unit Installation charges	995463	2	Nos	6,210.00	18%	2,235.6	12,420.00
2		Installation charges for VRV Indoor units.	995463	10	Nos	3,105.00	18%	5,589.0	31,050.00
3		Soft/Hard drawn Refrigerant Copper piping between Indoor & Outdoor units covered with suitable Nitrile Rubber Insulation 13/19 mm thick .	995463	100	Rmt	1,966.50	18%	35,397.0	1,96,650.00
4		2 core 1.0 Sq.mm flexible control cable & PVC conduits to connect outdoor units.	995463	150	Rmt	134.10	18%	3,620.7	20,115.00
D		**PVC drain piping with supports, clamps and 6mm thick Nitrile rubber tube insulation of following sizes**							
1		32 mm dia	995463	80	Rmt	248.40	18%	3,577.0	19,872.00
2		R-410A Gas.	995463	22	Kgs	931.50	18%	3,688.7	20,493.00
3		Indoor Unit Necessary Y Joints	995463	9	Nos	310.50	18%	503.0	2,794.50
4		Outdoor Unit Necessary Y Joints	995463	1	Nos	621.00	18%	111.8	621.00
5		Unit lifting shifting , Positioning Vaccumeising , Pressure Testing and Commissioning charges	995463	32	HP	1,035.00	18%	5,961.6	33,120.00
6		Cassette Indoor Unit supporting from roof threaded rod,nut & washer etc (structural support by Client)	995463	10	Nos	1,035.00	18%	1,863.0	10,350.00
7		Copper pipe supporting from roof threaded rod,nut & washer etc (structural support by Client)	995463	1	Lot	5,175.00	18%	931.5	5,175.00
8		Outdoor Unit MS stand stool type	995463	2	Nos.	8,280.00	18%	2,980.8	16,560.00
9		Civil work for Outdoor unit Leg	995463	2	Nos.	2,070.00	18%	745.2	4,140.00
E		**CABLE / PIPE TRAYS : Supply & Installation of pre-galvanized sheet steel perforated cable tray along with top cover. The cable tray shall include necessary supports and other accessories.**							
1		200mm wide x 100 mm height only outside building	995461	15	Rmt	879.30	18%	2,374.1	13,189.50
2		Scafholding arrangement for internal works	997319	1	Lot	12,420.00	18%	2,235.6	12,420.00
3		Supply & Installation of MS Supports for VRV IDU ETC	995463	300	Kg	186.30	18%	10,060.1	55,890.00
4		Transporation Charges	996511	1	lot	10,350.00	18%	1,863.0	10,350.00
A		**SUPPPLY OF VRF OUTDOOR UNITS**							
1		28HP Outdoor units	84159000	1	Nos	5,59,693.80	18%	1,00,744.9	5,59,693.80
B		**SUPPLY OF VRF INDOOR UNITS/AHU AND ACCESSORIES**							

1		1.0 TR Cassette Indoor unit with front panel and remote control	84159000	2	Nos	39,712.50	18%	14,296.5	79,425.00
2		1.5 TR Cassette Indoor unit with front panel and remote control	84159000	1	Nos	43,431.30	18%	7,817.6	43,431.30
3		2.5 TR Cassette Indoor unit with front panel and remote control	84159000	2	Nos	49,009.50	18%	17,643.4	98,019.00
4		4.0 TR Cassette Indoor unit with front panel and remote control	84159000	4	Nos	50,869.80	18%	36,626.3	2,03,479.20
5		Supply of 1.5Ton split AC	84159000	1	nos	36,949.50	18%	6,650.9	36,949.50
6		Supply of 1.Ton split AC	84159000	2	Nos	33,678.90	18%	12,124.4	67,357.80
C		**Installation charges**							
1		Outdoor unit Installation charges	995463	2	Nos	6,210.00	18%	2,235.6	12,420.00
2		Installation charges for VRV Indoor units.	995463	9	Nos	3,105.00	18%	5,030.1	27,945.00
D		**Installation charges for Floor Mounted type Air Handling Unit**		0	Nos				
1		Soft/Hard drawn Refrigerant Copper piping between Indoor & Outdoor units covered with suitable Nitrile Rubber Insulation 13/19 mm thick .	995463	90	Rmt	1,966.50	18%	31,857.3	1,76,985.00
E		**Control Cabling**							
1		2 core 1.0 Sq.mm flexible control cable & PVC conduits to connect outdoor units.	995463	150	Rmt	134.55	18%	3,632.9	20,182.50
F		**PVC drain piping with supports, clamps and 6mm thick Nitrile rubber tube insulation of following sizes**							
1		32 mm dia	995463	70	Rmt	248.40	18%	3,129.8	17,388.00
2		R-410A Gas.	995463	18	Kgs	931.50	18%	3,018.1	16,767.00
3		Indoor Unit Necessary Y Joints	995463	8	Nos	310.50	18%	447.1	2,484.00
4		Outdoor Unit Necessary Y Joints	995463	1	Nos	621.00	18%	111.8	621.00
5		Unit lifting shifting , Positioning Vaccumeising , Pressure Testing and Commissioning charges	995463	28	HP	1,035.00	18%	5,216.4	28,980.00
6		Cassette Indoor Unit supporting from roof threaded rod,nut & washer etc (structural support by Client)	995463	9	Nos	1,035.00	18%	1,676.7	9,315.00
7		Copper pipe supporting from roof threaded rod,nut & washer etc (structural support by Client)	995463	1	Lot	5,175.00	18%	931.5	5,175.00
8		Outdoor Unit MS stand stool type	995463	2	Nos.	8,280.00	18%	2,980.8	16,560.00
9		Civil work for Outdoor unit Leg	995463	2	Nos.	2,070.00	18%	745.2	4,140.00
G		**CABLE / PIPE TRAYS : Supply & Installation of pre-galvanized sheet steel perforated cable tray along with top cover. The cable tray shall include necessary supports and other accessories.**							
1		200mm wide x 100 mm height only outside building	995461	15	Rmt	879.60	18%	2,374.1	13,189.50
2		Scafholding arrangement for internal works	997319	1	Lot	12,420.00	18%	2,235.6	12,420.00
3		Supply & Installation of MS Supports for VRV IDU ETC	995463	200	Kg	186.30	18%	6,706.8	37,260.00
4		Transporation Charges	996511	1	lot	10,350.00	18%	1,863.0	10,350.00
5		Errection of 1.5ton SplitAC with drain and copper tube etc	995463	1	nos	12,730.50	18%	2,291.5	12,730.50
6		Errection of 1 ton SplitAC with drain and copper tube etc.	995463	2	nos	12,730.50	18%	4,587.0	25,461.00

Total Amount Before Tax(Rs) :	31,07,483.1
GST Value :	5,59,347.0
Po Value (Rs) :	**36,66,830.1**

Total Amount in Words: **Thirty Six Lakhs Sixty Six thousand Eight Hundered and Thirty only**

Prepared By	Verified By	Approved By
Parthiban R	Arunkumar B N	Jayakishore L
Purchase Engineer	Plant Engineering -Head	AVP Operations

Jayakishore Digitally signed by Jayakishore Date: 2026.03.24 13:17:26 +05'30'

Terms and Conditions:

1. Manufacturer warranty clearly pass on for the Items supplied
2. All the items should supply with specific brand mentioned in the quote
3. Items must be deliver on time as specified in the Po

Billing to:
YANVIOR TECHNOLOGIES PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

Shipping to:
YANVIOR TECHNOLOGIES PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

Prepared By Parthiban R Purchase Engineer	Verified By Arunkumar B N Plant Engineering -Head	Jayakishore Digitally signed by Jayakishore Date: 2026.03.24 13:17:42 +05'30' Approved By Jayakishore L AVP Operations