YANVIOR TECHNOLOGIES PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

Purchase Order

Supplier Code
Supplier Name and Address:

Vat Tech Enggineering . Pvt Ltd

No 38, Karpagambal Nagar
Nandhivaram Guduvancherri 603202
Tamilnadu,India
Email:
GST: 33AAECV6181C1ZI

PO Number : PO/26-27/0003
PO Date : 01-04-2026
Payment terms : **30% Advance with PO**
60 % Against delivery of materials at site
10% After testing and commisioning
AC VRF and AHU unit 100% Advance payment

Delivery time : **4 weeks**
Mode of Transport: **Road**
Incoterms : **Deliver to Sricity**

GST : **37AAACN9960D2ZA**

Please supply the following materials subject to terms and conditions. Kindly acknowledge receipt of this order

Sl.No	Item Code	Description	HSN/SAC code	Qty	UOM	Unit price (Rs)	GST% Rate	GST% Amount	Amount in (Rs)
		33TR AHU							
A		**VRF OUTDOOR UNITS**							
1		40HP Outdoor units	84159000	2	Nos	8,14,674.60	18%	2,93,282.9	16,29,349.20
		VRF INDOOR UNITS							
2		33TR-12000CFM, Floor mounted AHU,Double skin, Thermal barrier, DX cooling coil, 2circuit, 16.5TRx2Nos, with R.Air mixing box	84159000	2	Nos	7,96,500.00	18%	2,86,740.0	15,93,000.00
3		Electronic expansion valve kit	84818050	4	Nos	28,327.50	18%	20,395.8	1,13,310.00
4		Wired remote control for AHU	84159000	2	Nos	4,050.00	18%	1,458.0	8,100.00
5		Supply of Refnet for AHU	84159000	2	Nos	7,650.00	18%	2,754.0	15,300.00
II		**ANNEXURE B :INSTALLATION, TESTING & COMMISSIONING:**							
1		**Installation charges**							
a		Outdoor unit Installation charges	995463	2	Nos	9,000.00	18%	3,240.0	18,000.00
c		Installation charges for Floor Mounted type Air Handling Unit	995463	2	Nos	9,000.00	18%	3,240.0	18,000.00
2		**Soft/Hard drawn Refrigerant Copper piping(16G/19G) between indoor & Outdoor units covered with suitable NItrile Rubber insulation 13/19 mm thick .**							
c		5/8" (15.88 mm) with 13mm thick insulation	995463	24	Rmt	850.50	18%	3,674.2	20,412.00
d		3/4" (19.08 mm) with 13 mm thick insulation	995463	36	Rmt	1,170.00	18%	7,581.6	42,120.00
f		1 1/8" (28.58 mm) with 19 mm tick insulation	995463	24	Rmt	1,620.00	18%	6,998.4	38,880.00
g		1 3/8" (34.9 mm) with 19 mm tick insulation	995463	4	Rmt	2,610.00	18%	1,879.2	10,440.00
h		1 5/8" (41.3 mm) with 19 mm tick insulation	995463	32	Rmt	3,690.00	18%	21,254.4	1,18,080.00
3		**Control Cabling**							
a		2 core 1.0 Sq.mm flexible control cable & PVC conduits to connect outdoor units.	995463	90	Rmt	144.00	18%	2,332.8	12,960.00
4		PVC drain piping with supports, clamps and 6mm thick Nitrile rubber tube insulation of following sizes							
a		32 mm dia	995463	10	Rmt	261.00	18%	469.8	2,610.00
5		R-410A Gas.	995463	60	Kgs	945.00	18%	10,206.0	56,700.00
6		Indoor Unit Necessary Y Joints	995463	2	Nos	315.00	18%	113.4	630.00
7		Outdoor Unit Necessary Y Joints	995463	2	Nos	630.00	18%	226.8	1,260.00
8		Unit lifting shifting , positioning Vaccumeising , Pressure testing and Commissioning charges	995463	80	hp	1,350.00	18%	19,440.0	1,08,000.00
11		Outdoor Unit MS stand stool type	995463	4	Nos.	11,250.00	18%	8,100.0	45,000.00
12		Civil work for Outdoor unit Leg	995463	4	Nos.	4,050.00	18%	2,916.0	16,200.00
13		**CABLE / PIPE TRAYS : Supply & Installation of pre-galvanized sheet steel perforated cable tray along with top cover. The cable tray shall include necessary supports and other accessories.**							
a		200mm wide x 100 mm height only outside building	995461	12	Rmt	1,080.00	18%	2,332.8	12,960.00
b		300mm wide x 100 mm height only outside building	995461	28	Rmt	1,260.00	18%	6,350.4	35,280.00
14		AHU Electrical Starter panel with all controls	995461	2	Nos	1,03,500.00	18%	37,260.0	2,07,000.00
15		Control wire between AHU starter panel to AHU Motor	995461	40	Rmt	198.00	18%	1,425.6	7,920.00

30/6

2nd pay hawt

16		Supply & installation of Rectangular duct - 24 G	995463	460	Sqm	1,260.00	18%	1,04,328.0	5,79,600.00
17		Supply & installation of Rectangular duct - 22 G	995463	360	Sqm	1,170.00	18%	75,816.0	4,21,200.00
18		Supply & installation of 10mm thick Acoustic Nitrile Insulation	995463	120	Sqm	855.00	18%	18,468.0	1,02,600.00
19		Supply & installation of 19mm thick Thermal Nitrile Insulation	995463	820	Sqm	720.00	18%	1,06,272.0	5,90,400.00
20		Supply & installation of Fiber glass cloth raping with weather proof paint coating ONLY OUTSIDE BUILDING	995463	220	Sqm	270.00	18%	10,692.0	59,400.00
21		Supply & Installation of Supply Air Grill with collar damper -	995463	24	Nos	3,690.00	18%	15,940.8	88,560.00
22		Supply & Installation of Return Grill-600x600	995463	11	Nos	5,580.00	18%	11,048.4	61,380.00
23		Supply & Installation of GI Volume control duct damper	995463	1.5	Sqm	12,150.00	18%	3,280.5	18,225.00
24		Supply and Installation of Canvass (Flexible Canvass)	995463	4	Nos	3,150.00	18%	2,268.0	12,600.00
25		Scafholding arrangement for internal works	995463	1	Lot	40,500.00	18%	7,290.0	40,500.00
26		Supply & Installation of MS Supports for S.air and R.air Ducts	995463	170	Kg	225.00	18%	6,885.0	38,250.00
27		Transporation Charges	996511	1	lot	31,500.00	18%	5,670.0	31,500.00
							Total Amount Before Tax(Rs) :		61,75,726.2
							GST Value		11,11,630.7
							Po Value (Rs) :		72,87,357

Total Amount in Words: **Seventy Two Lakhs Eighty Seven thousand Three Hundred and Fifty Seven only**

Terms and Conditions:

1. Manufacturer warranty clearly pass on for the items supplied
2. All the items should supply with specific brand mentioned in the quote
3. Items must be deliver on time as specified in the Po

Billing to:

YANVIOR TECHNOLOGIES PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

Shipping to:

YANVIOR TECHNOLOGIES PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

Prepared By
Arunkumar B N
Consultant

Verified By
Jayakishore L
AVP Operations

Approved By
Sudharsan M
COO

2nd pay TDR Tax