CHINTALAPATI HOLDINGS PVT LTD
18, BLG3, ILABSCENTRE
SOFTWAREUNITSLAYOUT,MADHAPUR,
Ranga Reddy, Telangana, 500081

PROFORMA INVOICE

Supplier Code :
Supplier Name and Address:
NUCLEUS SATELLITE COMMUNICATIONS (MADRAS) PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati Andhra Pradesh-517541
GST: 37AAACN9960D2ZA

PI NO: PI /2025-26/005
PI Date 07.03.2026
Reference : **PO/25-26/0087**
Mode of Transport: NA
Incoterms : NA

GST : **36AABCC5085D1ZV**

Please supply the following materials subject to terms and conditions. Kindly acknowledge receipt of this order

Sl.No	Description	HSN/SAC code	Qty	UOM	Unit price (Rs)	Amount in (Rs)
1	**Laying of Storm water Drains** **(Total Length of Drain considered - 900 RMT)** Earth work excavation by manually/mechanical means for Spun Pipeline laying and Manholes etc and depositing the earth on bank with an initial lead of 50m and initial lift of 2.00m in all types of soils up to Soft Disintegrated Rock (SDR) like loamy, and clayey soils like black cotton soils, red earth, ordinary gravel soils, mixture of gravel and S.D.R like shales, ordinary gravel stony earth and earth mixed with fair sized boulders, under water, liquid mud etc. including shoring, strutting,pumping, dewatering, dressing compacting, machinery hire charges,seignoarges charges, etc., including all incidental, operational and labour charges, all tools and plants, watering etc. complete for finished item of work. Including disposing of surplus earth within site premises for all leads and lifts, as directed by the engineer in charge	9954	200	CUM	227	45,450
2	Levelling of Excavated soil to acheive 1:300 slope for laying the spun pipeline, Compactting the soil Earth work excavation by manually/mechanical means for foundations, sumps,machine fdn,trenches etc and depositing the earth on bank with an initial lead of 50m in all types of soils up to a depth of 2.0m to 4.0m lvl in Soft Disintegrated Rock (SDR) like loamy, and clayey soils like black cotton soils, red earth, ordinary gravel soils, mixture of gravel and S.D.R like shales, ordinary gravel stony earth and earth mixed with fair sized boulders, under water, liquid mud etc including shoring, strutting, pumping, dewatering, dressing compacting, machinery hire charges, seignoarges	9954	150	cum	136	20,453

	charges, etc., including all incidental, operational and labour charges, all tools and plants, watering etc. complete for finished item of work. Including disposing of surplus earth within site premises for all leads and lifts, as directed by the engineer in charge					
3	Refilling with useful available good excavated earth (including rock) in trenches, sides of foundations and basement in layers not exceeding 15cm thick, including consolidating each deposited layer by power compactors, dressing, watering and ramming upto OMC 95-98% , (proctor density as per morth specifications) including testing 5-6nos at every 400cum in each layers including all operational, incidental, labour charges, hire charges of T & P and machinery, watering, lead and lift charges etc., complete for finished item of work. as directed by the engineer incharge	9954	120	Cum	136	16,362
4	**a) with available excavated soil** Supply and laying of 450mm Dia x 2500 mm length spun pipes manufactured accorsing to IS 458: 2003, including taxes unloading and laying using heavy machinery including all operational, incidental, labour charges, hire charges of T & P and machinery, watering, lead and lift charges etc., complete for finished item of work. as directed by the engineer incharge	9954	900	RMT	2,182	1,963,440
5	Disposal of the Excess soil by mechanical means using tippers machinery etc from Foundations, Debris, etc., towards low lying areas of inside site premises inclusive of all incidental operational labour charges, all loading and unloading, consoildation in layers, Transportation,including all leads, lifts and all Taxes, all types of tools plants and machinery, hire charges of machinery etc., complete for finished item of work. as directed by engineer incharge	9954	80	Cum	91	7,272
6	**B.Man holes** Providing Plain cement concrete in (1:4:8) proportion for foundations and under flooring using 40mm size hard granite metal from approved quarry including cost and conveyance of all materials like cement, sand, coarse aggregate, water to site, including cost of centering and shuttering charges, de-shuttering charges, including seigniorage charges , all incidental,operational and labour charges, all types of taxes, GST,machine mixing, laying compacting, placing and vibrating to required level, all lead and lift charges,	9954	15	Cum	5,454	81,810

	all type of tools and plant, hire charges of machinery, water, curing etc., and including cost of cement, complete for finished item of work as directed by engineer incharge					
7	**C.MASONRY WORKS.** Red Brick masonry walls of any thickness for below plinth, super structure, parapet walls etc., with CM (1:6) prop (Cement:sand) using standard Red brick sizes from approved source having minimum crushing strength of 5 N/sq.mm. including cost and conveyance of all materials like cement, sand, bricks, water etc., seigniorage charges, all incidental and operational, labour charges like mixing cement mortar, scaffolding charges, lift charges, curing etc., of all heights complete for finished item of work.	9954	65	Cum	9,090	590,850
8	**D.PLASTERING WORKS** Providing impervious coat to exposed Massonry walls surfaces to required slopes with CM (1:5) prop. 20mm thick mixing with water proofing compound of approved compound from reputed manufacturers like FOSROC or SIKA or Dr. Fixit, including cost and conveyance of materials like cement, sand, water proofing compound etc., to site, seigniorage charges and labour charges rendering smooth , curing lift charges etc., complete but including cost of Cement, for finished item of	9954	300	Sqm	455	136,350
9	**E.MISCELANEOUS WORKS** Supplying & Providing 50 mm thk FRPManhole covers of capacity 5MT including cost and conveyance of all materials like cement, sand, water etc to site, cost of seigniorage charges and all other taxes, GST, on all materials, and including all operational, incidental charges and labour charges for mixing mortar, finishing, fixing in position, scaffolding,Form work, lift charges, curing, Complete finished item of work as per Drawing and as directed by Engineer - in - charge .	9954	30	Nos	2,727	81,810
10	**F.HARVESTING PITS** Water harvesting pits as per drawing with one layer river sand,one layer with 20mm metal layer and last layer with 40mm metal each of required thickness including excavtion of soil and disposing surplus earth within sit premisis as directed by the engineer incharge	9954	8	Nos	22,725	181,800
11	Providing and fixing factory made precast RCC perforated drain covers, having concrete of strength not less than M-25, of size 1000 x 450x50	9954	7.65	Sqm	1,818	13,908

	mm, reinforced with 8 mm dia four nos longitudinal & 9 nos cross sectional T.M.T. hoop bars, including providing 50 mm dia perforations @ 100 to 125 mm c/c, including providing edge binding with M.S. flats of size 50 mm mm x 1.6 mm complete, all as per direction of Engineer-in-charge.					

	Total Amount Before Tax(Rs)	3,139,504
	GST Value	565,111
	Po Value (Rs) :	3,704,615
	50% Advance Payable as per	**1,569,752**

Total Amount in Words: Fifteen Lakh Sixty Nine Thousand Seven Hundred and Fifty Two Only.

Authorised Signatory