NUCLEUS SATELLITE COMMUNICATIONS (MADRAS) PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

Purchase Order

Supplier Code :
Supplier Name and Address:

SVN ENGINEERING SERVICES

No:1-190, Mallavaripalem East,
Sri City, Satyavedu Mandal,
Tirupathi District, AP-517588
Email:svnengineeringservices25@gmail.com
GST: 37AQOPN2483N1Z0

PO Number : **PO/25-26/0093**
PO Date : **10-03-2026**
Payment terms : **50% Advance With PO & 50% After completion of work**
Delivery time : **4 weeks**
Mode of Transport: **NA**
Incoterms : **NA**

GST : **37AAACN9960D2ZA**

Please supply the following materials subject to terms and conditions. Kindly acknowledge receipt of this order

Sl.No	Item Code	Description	HSN/SAC code	Qty	UOM	Unit price (Rs)	GST%		Amount in (Rs)
							Rate	Amount	
		Shop Floor Partition Work							
		A.Modular Wall Partition							
1		Supply and Installation of Tounge and Groove Puff Panels of minimum 50 mm Thk. Both side cladding of PPGI sheet of 0.6mm thick Galvanize iron sheets (hot dipped with zinc coating of 120 gsm) with PUF as infill of density not less than 40 Kg/m3 . Hidden Tongue and Groove with Necessary stiffners to be provided as per manufacturer's standard and complete in all respects.	995441	1,600	Sq.Ft	260.00	18%	74,880.00	4,16,000.00
		Accessories							
2		Providing and Installation of Wall partition Accessories,	995441	1600	Sq.Ft	15.00	18%	4,320.00	24,000.00
3		Providing and Installation of ' C ' Flashing for Wall having Grith-155 MM	995441	50	Rmt	700.00	18%	6,300.00	35,000.00
		Providing and Installation of Inner PVC Coving for Wall to Wall	995441	18	Rmt	285.00	18%	923.40	5,130.00
		Providing and Installation of Outer Aluminium Coving for Wall to Wall Grith-150 MM	995441	18	Rmt	785.00	18%	2,543.40	14,130.00
		B.Fixed Glass Partition							
1		Providing and Installation of 10 or 8 mm thick toughened glass,on inside & necessary adhesive tape and silicon sealant for fitment.	995441	3375	Sq.Ft	330.00	18%	2,00,475.00	11,13,750.00
2		Providing and Installation of Powder coated Aluminium Frame having 1.2 mm thickness	995441	3375	Sq.Ft	175.00	18%	1,06,312.50	5,90,625.00
		C.Modular Walkable Ceiling							
1		Supply and Installation of sandwiched GI Powder coated walkable false ceiling of minimum 50mm Thk. Both side cladding of PU powder coated (60-80 microns) 0.6 mm thick Galvanize iron sheets (hot dipped with zinc coating of 120 gsm) with PUF as infill of density not less than 40 Kg/m3 .The load bearing capacity to be not less than 150kg/m2. The clean room panel should meet the Euro classes minimum reaction to fire B-s3,d0. Necessary stiffners to be provided as per manufacturer's standard and complete in all respects including, supports, hangers, sealants, etc.	995441	33870	Sq.Ft	249.00	18%	15,18,053	84,33,630.00
2		Providing and Installation of Ceiling Panel Aluminium T-grid, Turn Buckle for every 3 Mtr Intervals	995441	1190	Rmt	765.00	18%	1,63,863	9,10,350.00
3		Providing and Installation of Threared Rod 4 to 5 Rmt each support, GI Clamp for Purlin support, Screw, Nut, washer & Silicon etc.	995441	33900	Sq.Ft	15.00	18%	91,530	5,08,500.00

4		Providing and Installation of 50 x 50 mm metallic coving corners with Epoxy Powder coated/PU powder coated (60-80 microns) finish of matching colour with panel / ceiling and air tight with sealant at wall to wall with corner 2D or 3D	995441	20	Nos	200.00	18%	720	4,000.00
5		Providing and Installation of Aluminium/GI Coving for Ceiling to Gridth 150 MM	995441	100	Rmt	725.00	18%	13,050	72,500.00
		Cutouts							
6		Cutouts for Light Fixtures and Diffucers , consider 150 Lights and 150 Diffucers	995441	300	Nos	210.00	18%	11,340	63,000.00
7		C Flashing for Cutouts - with Powder Coated	995441	720	Rmt	225.00	18%	29,160	1,62,000.00

Total Amount Before Tax(Rs) :		1,23,52,615
GST Value	:	22,23,471
Po Value (Rs)	:	**1,45,76,086**

Total Amount in Words: **One Crore Forty Five lakhs Forty six thousand Seven hundred and Forty Five only**

B. N. Dev.

Prepared By

Jayakishan. L

Verified By

Approved By

Terms and Conditions:

1. Warranty 5 year for the items supplied
2. All the items should supply with specific brand mentioned in the quote
3. Items must be deliver on time as specified in the Po

Billing to:
NUCLEUS SATELLITE COMMUNICATIONS (MADRAS) PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

Shipping to:
NUCLEUS SATELLITE COMMUNICATIONS (MADRAS) PVT LTD
465,CITRUS DRIVE
MOPURU PALLI VILLAGE, SATHYAVEDU
Sri City,Tirupati
Andhra Pradesh-517541

Prepared By	Verified By	Approved By
B. N. Reddy.	Jayakishore.L	